

ΕΛΛΗΝΙΚΗ ΔΗΜΟΚΡΑΤΙΑ Μόνιμη Αντιπροσωπεία της Ελλάδος στο ΝΑΤΟ			ΑΔΙΑΒΑΘΜΗΤΟ ΕΠΕΙΓΟΝ
Αρμόδιος:	Ασμχος (ΜΕ) Δημήτριος Κανταρτζόγλου		Βρυξέλλες, 27 Ιουνίου 2021
Τηλ.:	+32 2 707 6734		<b>А.П.:</b> 3442
Ηλεκ. Δνση:	d.kantartzoglou@grdel-nato.be		
ΠΡΟΣ:	-ΥΠΕΘΑ/ΓΔΑΕΕ/ΔΑΕΤΕ	(μ.η.)	
KOIN.:	-ΥΠΕΞ/Δ΄ Γεν. Δ/ντη		
	-ΥΠΕΞ/Δ2 Δ/νση		
	-ΓΕΕΘΑ/Γ2	(μ. ΓΕΕΘΑ)	
	-Υπουργείο Ανάπτυξης /Γενική Γραμματεία Εμπορίου Πλ.Κάνιγγος	(μ.η.)	
	-Υπουργείο Ανάπτυξης /Γενική Γραμματεία Βιομηχανίας /Δνση Διεθνών Βιομηχανικών Σχέσεων Πλ.Κάνιγγος	(μ.η.)	
	-Τεχνικό Επιμελητήριο Ελλάδος /Δνση Ε Επαγγελματικής Δραστηριότητας Νίκης 4	(μ.η.)	

ΘΕΜΑ:Πρόσκληση Υποβολής Προσφορών, IFB-CO-115401-TSGT-ISS, Διαγωνιστικής Διαδικασίας,<br/>«NATO Transportable Satellite Ground Terminals Third Generation (TSGT3G) and Upgraded<br/>Transportable Satellite Ground Terminals (UTSGT) In-Service Support Activities»

1. Διαβιβάζεται, συνημμένως, Πρόσκληση Υποβολής Προσφορών (invitation For Bid/IFB) και σχετικά αυτής, εν θέματι διαγωνιστικής διαδικασίας (International Competitive Bidding/ICB), εκ μέρους NCIA, ως φιλοξενούντος έθνους.

2. Καταληκτική ημερομηνία υποβολής προσφορών ορίζεται η <u>31<sup>η</sup> Αυγούστου τ.έ., 14:00 τ.ώ.</u>

3. Ενδιαφερόμενες εταιρίες αναζητήσουν πληροφορίες μέσω καθοριζομένου σημείου επαφής (Point of Contact/POC, βλ. παρ. 17 προσκλήσεως).

4. Παρακαλούμε για τις ενέργειές σας.

λαμπρίδης

Συν. Σελ: 736 + 2 ηλεκτρονικά αρχεία φύλλων δεδομένων

ΑΚΡΙΒΕΣ ΑΝΤΙΓΡΑΦΟ Ο υπάλληλος της Μ.Α. ΝΑΤΟ Σταύρος Τσάκωνας ΕΠ&ΠΛ.Α΄

Part #	Description	Mftr
N5245A	Test Equipment, Keysight (Agilent) PNX-X Network Analyzer	
E8257D	PSG Analog Signal Generator w/ Rackmount Flange	Agilent
E8257D	Signal Generator, Analog w/ Rackmount Flange	Agilent
N9020A	Spectrum Analyzer w/ Rackmount Flange	Agilent
	Spectrum Analyzer Phase Noise App	Agilent
N4692A	Electronic Calibration Module	Agilent
53150A	Frequency Counter	Agilent
E4418A	Power Meter w/ Rackmount Flange	HP
E4412A	Power Sensor	Agilent
77	Multimeter	Fluke
82357B	USB TO GPIB Adaptor	Agilent
T-BERD 6000A V2	Data Tester/Comms Analyzer	Viavi
	Misc Cables and components for integration	
SLSLL18-NMNM50.00F	RF Test Cable	Times Microwave
SLSLL18-NMNM50.00F	RF Test Cable	Times Microwave
SLSLL18-NMNM28.00F	RF Test Cable	Times Microwave
SLSLL18-NMNM28.00F	RF Test Cable	Times Microwave
SLSLL18-NMNM28.00F	RF Test Cable	Times Microwave
SLSLL18-NMNM20.00F	RF Test Cable	Times Microwave
SLSLL18-NMNM20.00F	RF Test Cable	Times Microwave
SLSLL18-NMNM10.00F	RF Test Cable	Times Microwave
SLSLL18-NMNM10.00F	RF Test Cable	Times Microwave
SLSLL18-NMNM10.00F	RF Test Cable	Times Microwave
SLSLL18-NMNM10.00F	RF Test Cable	Times Microwave
SLSLL18-NMNM06.00F	RF Test Cable	Times Microwave
SLSLL18-NMNM06.00F	RF Test Cable	Times Microwave
SLSLL18-NMNM06.00F	RF Test Cable	Times Microwave
SLSLL18-NMNM06.00F	RF Test Cable	<b>Times Microwave</b>
	Transit Cases	Times Microwave
Latitude 5420 Rugged	Dell laptop for ATE	Dell
	Rack Mount Flange Kits (may be attached to equipment)	Agilent

SN			Shipped
	Qty	UМ	From
MY49151183	1	EA	NY
US51110154	1	EA	NY
MY46130369	1	EA	NY
MY46472181	1	EA	NY
	1	EA	NY
MY46180389	1	EA	NY
US40500891	1	EA	GCE
GB37170943	1	EA	NY
MY50360008	1	EA	GCE
78380416	1	EA	GCE
MY48200635	1	EA	GCE
10246, 10241	2	EA	NY
	1	EA	NY
#1	1	EA	NY
#2	1	EA	NY
#3	1	EA	NY
#4	1	EA	NY
#5	1	EA	NY
#6	1	EA	NY
#7	1	EA	NY
#8	1	EA	NY
#9	1	EA	NY
#10	1	EA	NY
#11	1	EA	NY
#12	1	EA	NY
#13	1	EA	NY
#14	1	EA	NY
#15	1	EA	NY
	2	EA	GCE
3C3KTG2	1	EA	GCE
	5	SET	NY



NATO Communications and Information Agency

# DSO TSGT3G DCIS, DAC Annual Preventive Maintenance Inspection ADVANCE PMI EBA Work Order NO:

NCIA CSSC ENM TRS/SAS			
Revision 2.3			
Date	01 Feb 2021		



# 3rd Level Annual Preventive Maintenance Inspection Procedure & Checklist

#### **ADVANCE PMI**

Section Owner:	Transmission Systems SATCOM	Document Writer	NIC B-4 Ruhi Cetin	
Version:	VER. 2.2	Document Controller and editor	NIC B-4 Ruhi Cetin NIC B-5 Andreas Kunisch	
<b>Creation Date:</b>	02 Jul 2020	Document Approval	NIC A-2 John Parris	
Description:	This Procedure& chec should perform 3rd le Systems. A System Risk Analys kept to a minimum.	Iecklist gives detail of the set up how a Satellite Communication Technician Ievel Annual Preventive Maintenance on DAC, DCIS DSO TSGT G3 Satellite Iysis (or Last Minute Risk Assessment) has to be completed, to ensure that risks		
Copyright and Distribution:	All rights reserved NCL CSSC/EMB/TSS SATC	A. COM Brunssum/NLD		

# 1.0 SYSTEM Annual PMI Summary

Work Package TRS			
Number:	1		
Title:	Perform Preventive Maintenance Inspection (PMI) on DSO TSGT (OL??)		
Location:	TSS-CSSC BRUNSSUM		
Priority:	1		
PMI Performed on			
Technician#1	Signature:		
Technician#2	Signature:		
Status	Fully Operational		
Limitations/Tasks	Listed Below		

Task	Status Open/Completed	(INC)Incident Number	Task Description	Remarks
1			Performed Annual preventive maintenance inspection in accordance with set procedures.	
2			Corrective Action for broken items.	
3			Upgrade EBEM Modem Battery	

4		Electrical Safety checks	
5		TE Calibration	
6		Fiber rolls checks	

#### 1.1 SYSTEM INITIAL ASSESMENT/STATUS CHECKS

#### **1.2 UPS FUNCTIONAL CHECKS**

	PROCEDURE / REPORT OF TEST Nº 1.1 & 1.2						
TEST NAME: Initial         ELEMENT UNDER TES           Status         Status		ELEMENT UNDER TEST: COMPLETE S	SYSTEM	PROJECT: TSGT-DSO			
NUMBER	TEST SEQUENCE		EXPECTED RESULT	RESULT	REMARKS		
	Pr	e-System Checks					
1.	ഞ്ഞെങ്കുstem installation performed in accordance with installation			☐ Passed ☐ Failed			
2.	Check system grounding connectivity.			□ Passed □ Failed			
3.	Check Lightning roads and lightning connectivity.			☐ Passed ☐ Failed			
4.	Checkemarteau.corrosion, or any defect, rust on the T2 shelter and on the			☐ Passed ☐ Failed			
5.	<b>©⊉splener</b> bsic	le, roadside, cabin entry and all ETB's Dampers/Strut on the		□ Passed □ Failed			

	PROCEDURE / REPORT OF TEST Nº 1.1 & 1.2					
TEST NAME: Initial Status		ELEMENT UNDER TEST: COMPLETE S	ELEMENT UNDER TEST: COMPLETE SYSTEM		PROJECT: TSGT-DSO	
6.	Visual Check	curbside, roadside, cabin entry EMI shielding/filtering.		□ Passed □ Failed		
7.	Visual Check	T2 Antenna clamps and waveguide system for any defect.		□ Passed □ Failed		
	Pr	e-Power on Checks				
1.	Check Mains Power ETB Power connectors and confirm them that they are not corroded and not lose or broken.			Passed      Failed		
2.	Confirm the Emergency Power Disconnect Switch (S1) located on the P-ETB is not engaged.			Passed  Failed		
3.	Confirm the Emergency Power Disconnect Switch (S6) located above the rear Road side wheel well of the TSGT Container is not engaged.			Passed      Failed		
4.	Confirm all circuit breakers located in the Clean and Dirty Power Distribution Panels are in the OFF position.			Passed      Failed		
5.	Confirm all Inverter Module Input and Output circuit breakers and Inverter Chassis circuit breakers are in the OFF position.			Passed      Failed		
	System Ini	tial Power On Checks				

PROCEDURE / REPORT OF TEST Nº 1.1 & 1.2					
TEST N	I <b>AME:</b> Initial Status	ELEMENT UNDER TEST: COMPLETE S	SYSTEM	STEM PROJECT: TSGT-DSO	
1.	Connect MAIN Main Power Ir breaker at the Panel, verify t 10%). Open c 3Phase Voltag 3Phase Curre 3Phase Powe 3Phase Frequ	A POWER from the PGS or Commercial Power Socket to the nput on the Power ETB. Power up the system from main circuit AC Power Meter located in the Dirty Power Distribution hat the voltage is within the range 360 – 440VAC (400VAC ± heck and Print AC PWM screen on ASNMC GUI. ge : Vavg nt : Iavg r : KW hency: Freq.	AC PWM [Connected]           AC PWM           ab           VII ab (V)           409.5           Ia (A)           5.2           General           VII avg (V)           409.4           PF sign total	bc         [ca           VII bc         409.4           Ib         (A)           I         avg           I         avg	11 ca (V) 409.4 c (A) 5.2 hcy (Hz) 49.99
2.	Engage Emer located on the Circuit Breake	gency Stop button (Emergency Power Disconnect Switch (S1) P-ETB) if it is cutting all power to system and tripping mains ers.		☐ Passed ☐ Failed	
3.	Disengage En (S1) located o system.	nergency Stop button (Emergency Power Disconnect Switch n the P-ETB) restore CCT Breakers and apply power to		Passed 🗌 Failed	
4.	Power up ECU check all ECU	J's A&B (check if the temperature is below +4 degrees) and I's heating.		□ Passed □ Failed	
5.	Powers up All functioning pro <u>ECU</u> Tem Mode	ECU's in turn and check, if all of them are configured and operly. <u>A</u> perature : +23 degrees AUTO	Temperature : +23 degrees Mode : AUTO	<b>A</b> :	
6.	ECU Tem Mode	<u>B</u> perature : +23 degrees e : AUTO	Temperature : +23 degrees	В:	

		PROCEDURE / REPORT OF 1	EST № 1.1 & 1.2		
TEST N/ St	TEST NAME: Initial         ELEMENT UNDER TEST: COMPLETE SY           Status         Status		SYSTEM	PROJECT: TSGT-DSO	
			Mode : AUTO		
7.	<u>ECU</u> Temp Mode	<u> </u>	Temperature : +23 degrees Mode : AUTO	C:	
8.	Open Battery	Compartment and Check Batteries status.		Passed      Failed	
9.	Start the powe on and apply Final combine Maximum 2 R Minimum 5 Re	er-on procedure till the point that rectifiers have to be switched test procedure, d (7 EA) rectifiers Output. ectifier failure is acceptable for the UPS. ectifier can support the System.	54.4 VDC	VDC	
	Open/check a	nd Print UPS Rectifiers screen on ASNMC GUI.			

				PROCE	DURE / REPO	RT OF TEST N	№ 1.1 & 1.2				
TEST N/	AME: Initial atus		ELEN	IENT UNDE	R TEST: COM	PLETE SYSTE	М		PROJECT:	TSGT-DSO	
	H Rect	ifier [Connected] Rectifier er Rectifiers Alar duleComStatus_1 duleOk_1 duleEnabled_1 UtVoltage_1 putVoltage_1 putVoltage_1 anCurrent_1 anCurrent_1	ms Normal Disabled 240 54.5 5.2 54 19	moduleComSta moduleOk_2 moduleEnablec nputVoltage_2 outputVoltage putputCurrent meanCurrent_2	atus_2 Normal Normal d_2 Disabled 2 240 _2 54.4 _2 5.4 2 53 2 22	moduleComSta moduleOk_3 moduleEnablea inputVoltage_ outputVoltage outputCurrent meanCurrent_ temperature_	atus_3 Normal Normal d_3 Disabled 3 240 _3 54.5 t_3 5.1 _3 53 3 25	moduled moduled inputVo outputV outputQ meanCu tempera	ComStatus_4 Dk_4 Enabled_4 Itage_4 Voltage_4 Current_4 urrent_4 ature_4	Normal Normal Disabled 240 54.5 5.3 53 17	
		modu modu input outpi outpi mear temp	uleComStatus, uleOk_5 uleEnabled_5 tVoltage_5 utVoltage_5 utCurrent_5 nCurrent_5 perature_5	5 Normal Normal Disabled 239 54.5 5.5 55 21	moduleComSta moduleOk_6 moduleEnabled inputVoltage_0 outputVoltage outputCurrent meanCurrent_ temperature_0	Normal           Normal           d_6         Disabled           6         240           2-6         54.6           t_6         5.6           6         54           6         24	moduleComSt moduleOk_7 moduleEnable inputVoltage outputVoltage outputCurren meanCurrent temperature	tatus_7 No ed_7 Disa _7 2 e_7 54 nt_7 55 t_7 55 t_7 55 t_7 55	rmal abled 40 4.5 .1 53 26		
10.	Turn on Invert Inver Inver Inver Inver	ter #1: ter #2: ter #3: ter #4:	rd operatior	nal status.					Passee Passee Passee Passee	d 🗌 Failed d 🗌 Failed d 🔲 Failed d 🔲 Failed	



	PROCEDURE / REPORT OF TEST Nº 1.1 & 1.2								
TEST N/ St	<b>AME:</b> Initial tatus		ELEMENT U	NDER TEST: COMPI	LETE S	SYSTEM		PROJECT: TSGT-DSO	
13	Check if Unipo	ower Charge	er controller Battery Und	ler voltage set properl	у.	46.0 Volts DC	;	Passed      Failed	
	5.5	et data	and the second sec		😋. Set data	Concess of the last			-
		Adjust limits Battery type: 4 Blocks  No of batt branches: 1 Sattery FA Threshold: C Low C High Battery FA Threshold: C System spe	Battery settings       Boost limits     10       Boost interval weeks     40       Boost factor:     1       Itil limit:     V       12 limit:     V       C     Automatic boost       Temperature compensation       IF Temperature compensation       Temperature     0.7	Custom Boost	Set U1-U- © Norm C Boos C Test C Spar - Auto test © 0 ° C - Alarm limit Low volt High volt O, V. shu Load/bal Partial di	Adjust limits           ial         U1 normal:           ial         U1 normal:           values         V           u3 test         V           u3 test         V           u4 spare:         V           values         V           u1 c2 c3 c4 c5 c6           ts         alarm:           alarm:         V           u4 down V         T           tdiscon V         T           sconnection 2 [V]         sconnection 3 [V]           System specific limits         System specific limits	Battery settings       540     Symme       560     Symme       660     End volt       84ttery     <	Custom Boost           test limits           try limit; V           tage b.test V           44.1           time: min           0           for test           10           rtest (0-23)           0           ion: V           49.0           100           ture limit; degC           0           ge; V           255	
14.	Make sure Un limited to 40 A	hipower char	ger Buttery Current Limi	it is enabled and curre	ent	Battery curre	nt limit 40A	Passed 🗌 Failed	
15.	Check if Unipower Charger controller disables (LVDS) Remove Battery Connectivity/ Kill UPS before batteries completely drained.					43.5 Volts DC	;	Passed      Failed	
16.	Check if Unipo Complete Sys	ower Charge stem.	er controller disables (EF	PO Switch) Shutdown		43.0 Volts DC	;	□ Passed □ Failed	
17.	Maximum only Minimum 3 In	y 1 Inverter f verter can su	ailure is acceptable for t upply power to the Syste	the UPS. em.					

	PROCEDURE / REPORT OF TEST Nº 1.1 & 1.2						
TEST N/ Si	<b>AME:</b> Initial tatus	ELEMENT UNDER TEST: COMPLETE S	SYSTEM	PROJECT: TSGT-DSO			
18.	Turn on Clear the equipment all racks, all fit Power ON all initial power C	n power distribution panel circuit breakers and apply power to t racks circuit breakers. Verify that power has been applied to ts and not tripping. independent units by switching them ON and check all having ON status.		☐ Passed			
19.	Switch off CB capable on UF	1 on the Dirty Power Panel and check that the system is PS power for at least 5 minutes.	5 Min. > 44.0 V	Passed      Failed			
20.	MACS DELL Maintenance LAPTOP with ORION Software		Windows 7 Professional Operating system starts. AxxSys Orion Graphical User Interface starts up.	🗌 Passed 🔲 Failed			
21.	ACU (ANTEN	NA CONTROL UNIT) FOR T1	Boot sequence for T1	Passed      Failed			
22.	ACU (ANTEN	NA CONTROL UNIT) FOR T2	Boot sequence for T2	Passed      Failed			
23.	POWER DRIV	/E UNIT (PDU) T2	Driving Antenna	Passed      Failed			
24.	PMU OPERA	TION-T2	Initial Power up	Passed      Failed			
25.	T2 ANTENNA	SUBSYSTEM	Moving Antenna on Both Sector AZ/EL	🗆 Passed 🔲 Failed			
26.	EMS SERVER COMPUTER LMCa		EMS GUI operation Log GUI Revision. <mark>REV.2.1.12</mark>	Passed  Failed			
27.	EMSe 1 MOD	EM	Booting Modems without any alarm	Passed 🛛 Failed			

	PROCEDURE / REPORT OF TEST Nº 1.1 & 1.2						
TEST N/ St	<b>AME:</b> Initial tatus	ELEMENT UNDER TEST: COMPLETE S	SYSTEM	PROJECT: TSGT-DSO			
28.	EMSe 2 MOD	EM	Booting Modems without any alarm	□ Passed □ Failed			
29.	EMSe 3 MOD	EM	Booting Modems without any alarm	□ Passed □ Failed			
30.	EMSe 4 MOD	EM	Booting Modems without any alarm	Passed      Failed			
31.	ASNMC LCAr	n SERVER COMPUTER	Windows Win7 prof. operating system starts ASNMC GUI Interface starts. ASNMC VER.1.2.2 Beta iDirect GUI access	Passed  Failed			
32.	ASNMC DWS	CLIENT COMPUTER	Windows Win7 prof. operating system starts ASNMC GUI Interface starts. ASNMC VER.1.2.2 Beta iDirect GUI access	Passed  Failed			
33.	ASNMC VPN	ROUTER&SWITCH	Initial power up	Passed      Failed			
34.	ASNMC NU P	HONE	Initial Power up	Passed      Failed			
35.	ASNMC NR P	HONE	Initial Power up	Passed      Failed			
36.	ASNMC SWIT	ГСН	Initial Power up	Passed E Failed			
37.	VIASAT EBEN	M MODEM#1	Initial power up Check FW version Rev. <mark>02.03.02</mark>	Passed D Failed			

	PROCEDURE / REPORT OF TEST Nº 1.1 & 1.2							
TEST NA	<b>AME:</b> Initial tatus	ELEMENT UNDER TEST: COMPLETE S	SYSTEM	PROJECT: TSGT-DSO				
38.	VIASAT EBEN	M MODEM#2	Initial Power up Check FW version Rev. <mark>02.03.02</mark>	Passed      Failed				
39.	VIASAT EBEN	/ MODEM#3	Initial Power up Check FW version Rev. <mark>02.03.02</mark>	Passed      Failed				
40.	VIASAT EBEN	/ MODEM#4	Initial Power up Check FW version Rev. <mark>02.03.02</mark>	Passed      Failed				
41.	VIASAT EBEM MODEM#5		Initial Power up Check FW version Rev. <mark>02.03.02</mark>	☐ Passed ☐ Failed				
42.	LINE APMLIF	IERS	Initial power up	Passed      Failed				
43.	NETCLOCK T	FRS #1	Initial Power up	Passed      Failed				
44.	NETCLOCK T	FRS #2	Initial Power up	Passed      Failed				
45.	SPECTRA TF	RS DISTRIBUTION AMPLIFIER1	Initial Power up	Passed      Failed				
46.	SPECTRA TF	RS DISTRIBUTION AMPLIFIER2	Initial Power up	Passed      Failed				
47.	GPS ANTENN	IA	Initial Power up	Passed      Failed				
48.	(On DAC 1-4) DXC #1 & FO-MICE EQUIPMENT		Initial Power up	Passed  Failed				
49.	(On DAC 1-4) DXC #2 & FO	-MICE EQUIPMENT	Initial Power up	Passed 🗌 Failed				

	PROCEDURE / REPORT OF TEST Nº 1.1 & 1.2						
TEST N/ Si	AME: Initial atus	ELEMENT UNDER TEST: COMPLETE S	SYSTEM	PROJECT: TSGT-DSO			
50.	(On DCIS & D FDMA ROUTI	CAOC) ER #1	Initial Power up	Passed  Failed			
51.	(On DCIS & D FDMA Switch	CAOC) #1	Initial Power up	Passed  Failed			
52.	(On DCIS & D EMS ROUTEI	CAOC) R #2	Initial Power up	Passed  Failed			
53.	(On DCIS & DCAOC) EMS Switch #2		Initial Power up	Passed  Failed			
54.	Check Fiber F	Patch Panel and fiber connectors	Wiring status.	Passed      Failed			
55.	ORION SYST AMP#1 16 PC	EM MANAGEMNET SUB SYSTEM DRT	Initial Power up	Passed  Failed			
56.	ORION SYST	EM MANAGEMNET SUB SYSTEM H	Initial Power up	Passed  Failed			
57.	BUC A (BLOC	CK UP CONVERTER) for T1	Initial Power up	Passed      Failed			
58.	BUC SWITCHING UNIT for T1		Initial Power up	Passed  Failed			
59.	BUC B (BLOCK UP CONVERTER) for T1		Initial Power up	Passed  Failed			
60.	BUC A (BLOC	CK UP CONVERTER) for T2	Initial Power up	Passed      Failed			

	PROCEDURE / REPORT OF TEST Nº 1.1 & 1.2						
TEST N/ St	AME: Initial tatus	ELEMENT UNDER TEST: COMPLETE S	SYSTEM	PROJECT: TSGT-DSO			
61.	BUC SWITCH	IING UNIT for T2	Initial Power up	Passed      Failed			
62.	BUC B (BLOC	CK UP CONVERTER) for T2	Initial Power up	Passed  Failed			
63.	BDC A (BOCK	COWN CONVERTER) for T1	Initial Power up	Passed  Failed			
64.	BDC SWITCH	IING UNIT for T1	Initial Power up	Passed  Failed			
65.	BDC B (BOCk	COWN CONVERTER) for T1	Initial Power up	Passed  Failed			
66.	BDC A (BOCK DOWN CONVERTER) for T2		Initial Power up	Passed      Failed			
67.	BDC SWITCH	IING UNIT for T2	Initial Power up	Passed  Failed			
68.	BDC B (BOCk	COWN CONVERTER) for T2	Initial Power up	Passed  Failed			
69.	UPLINK EQU	ALIZER T1	Initial Power up	Passed  Failed			
70.	UPLINK EQU	ALIZER T2	Initial Power up	Passed  Failed			
71.	SSPA SUB SYSTEM #		Initial Power up	Passed  Failed			
72.	SSPA #A		Initial Power up	Passed  Failed			
73.	SSPA #B		Initial Power up	Passed  Failed			

	PROCEDURE / REPORT OF TEST Nº 1.1 & 1.2						
TEST N/ St	<b>AME:</b> Initial tatus	ELEMENT UNDER TEST: COMPLETE	SYSTEM	PROJECT: TSGT-DSO			
74.	LNA SUB SYS	STEM	Initial Power up	Passed  Failed			
75.	LNA #A		Initial Power up	Passed  Failed			
76.	LNA #B		Initial Power up	Passed  Failed			
77.	ANTI_ICING S	SYSTEM	Initial Power up	Passed      Failed			
78.	DEHYDRATO Check duty cy screen of pag	R rcle and operation of Dehydrator on ASNMC and attach print e.	Initial Power up	Dehydrator [Connected]       Image: Connected]         Dehydrator       Absorption unit1       Idle         Absorption unit1       Idle       Absorption unit2       In Use         AUI won't heat       Normal       AU2 won't heat       Normal         AUI won't cool       Normal       AU2 won't cool       Normal         Temperat. (°C)       27.2       Pressur. (mbar)       0.021         Low temperat.       Normal       Low pressure       Normal         High temperat.       Normal       High pressure       Normal         Warning present       Normal       Leaky system       Normal         Dew point       Riormal       Low line voltage       Normal         Duty cycle (%)       002       002       Normal			
79.	CONTAINER Check Contain of page.	TEMP ner temperature operation on ASNMC and attach print screen	Container t <sup>°</sup> [Connected] Container t <sup>°</sup> Container - High T <sup>°</sup> alarm Container - High T <sup>°</sup> warning Battery - High T <sup>°</sup> warning Battery - Low T <sup>°</sup> warning	Container temp. (°C) 17.31 Battery temp. (°C) 17.31 Battery temp. (°C) 17.98 37.5 Container - High T° alarm Normal Container - High T° warning Normal Battery - High T° warning Normal Battery - Low T° warning Normal			

	PROCEDURE / REPORT OF TEST Nº 1.1 & 1.2						
TEST N/ St	TEST NAME: Initial         ELEMENT UNDER TEST: COMPLETE SY           Status         Status		SYSTEM	PROJECT: TSGT-DSO			
80.	WEATHER REPORTING SYSTEM Check Weather St. operation on ASNMC and attach print screen of page.		Weather st.         [Connected]           Weather st.         Wind speed (kmph)         005.0           Wind direction         230.3         7° (°C)         007.5           Humidity (%)         -000.0         Pwr supply (VDC)         23.34				
81.	MISC. ALARMS T-2		Initial Power up	Passed  Failed			
82.	PGS (POWEF	R GENERATION SYSTEM) SUB SYSTEM	Initial Power up	Passed  Failed			
83.	PDU T1 ANTE	ENNA -OPERATION	Initial Power up AZ/EL drive	Passed      Failed			
84.	PMU OPERA	TION-T1	Initial Power up	Passed      Failed			
85.	HPA SUB SYS	STEM-T1	Initial Power up	Passed      Failed			
86.	HPA #A		Initial Power up	Passed      Failed			
87.	HPA#B		Initial Power up	□ Passed □ Failed			
88.	LNA SUB SYS	STEM_T1	Initial Power up	Passed  Failed			

	PROCEDURE / REPORT OF TEST Nº 1.1 & 1.2						
TEST NAME: Initial         ELEMENT UNDER TEST: COMPLETE           Status         ELEMENT UNDER TEST: COMPLETE		SYSTEM	PROJECT: TSGT-DSO				
89.	LNA#A		Initial Power up	Passed  Failed			
90.	LNA#B		Initial Power up	Passed  Failed			

#### 1.2.1 TEST EQUIPMENT FUNCTIONAL CHECKS

	PROCEDURE / REPORT OF TEST № 1.2.1						
TEST NAME:         Test Equipment           FUNCTIONAL CHECKS         ELEMENT UNDER TEST: TEST EQUIPMENT			QUIPMENT	PROJECT: TSGT-DSO			
STEP		TEST SEQUENCE	EXPECTED RESULT	RESULT	REMARKS		
1.	TELINC WAN	TESTER, TL2084EB S/N:6439323	Check power on status and CAL DUE DATE:				
2.	Keysight N191 SN: MY524900	3A POWER METER, 034	Check power on status and CAL DUE DATE:				
3.	Agilent 8481D S/N:MY410948	POWER SENSOR, 832	Check power on status and CAL DUE DATE:				
4.	Fluke 28 II S/N:		Check power on status and CAL DUE DATE:				
5.	NARDA99899 S/N:E-2316		Check power on status and CAL DUE DATE:				
6.	MCL Attenuator	3 db. S/N:0316	Check power on status and CAL DUE DATE:				

PROCEDURE / REPORT OF TEST Nº 1.2.1						
TEST NAME: FUNCTIONAL	Test Equipment CHECKS	ELEMENT UNDER TEST: TEST EQU	JIPMENT	PROJECT: TSGT-DSO		
	MCL Attenuator 6 db. S/N:0616		Check power on status and CAL DUE DATE:			
	MCL Attenuator 10 db. S/N:1016		Check power on status and CAL DUE DATE:			
	MCL Attenuator 20 db. S/N:2016		Check power on status and CAL DUE DATE:			
	Model 11708A 30db. S/N:63869		Check power on status and CAL DUE DATE:			
7.	BK PRECISION Spectrum Analyzer 2658A S/N: 2101031524		Check power on status and CAL DUE DATE:			
8.	JDSU DATA TESTER S/N:		Check power on status and CAL DUE DATE:			
9.	F/O 250meter HMA 4CH.SM S/N:9319/W054		Check power on status and CAL DUE DATE:			
10.	F/O 250meter H S/N:9319/W057	MA 4CH.SM	Check power on status and CAL DUE DATE:			

#### 1.2.1.1 HPA 750 W PMI ADVANCE

PROCEDURE / REPORT OF TEST №:1.2.1.1						
TEST NAME: HPA 750W PMI         ELEMENT UNDER TEST: Transmission TX           Advanced         Advanced			X Sub System	PROJECT: TSGT-DSO		
STEP		TEST SEQUENCE	EXPECTED RESULT	RESULT	REMARKS	
1.	Uninstall HPA #	A from its location and apply operational bench check.	Initial performance test.	Passed      Failed		
2.	Remove and Cle	ean Fan unit B1	ОК	□ Passed □ Failed		
3.	Check operation Replace fan afte	and the Replace B1 Fan unit. r 50.000 Hours of operation or every 4 years	ОК	☐ Passed ☐ Failed		
4.	Check operation Replace fan afte	and the Replace B2 internal Fan. r 50.000 Hours of operation or every 4 years	ОК	☐ Passed ☐ Failed		
5.	Place a fan repla	acement sticker inside the fan unit.	ОК	□ Passed □ Failed		
6.	Remove A1 Ass compound.	embly, 'Power Factor Module'. Clean and replace heatsink	Clean and replace heatsink compound.	□ Passed □ Failed		
7.	Remove A2 Moo heatsink compo	dule, Assembly, Power Processor, CCA, Clean and replace und.	Clean and replace heatsink compound.	□ Passed □ Failed		
8.	Remove A4 Moo C1&C2when uni	dule, Assembly, High Voltage Module. Replace Capacitors t is noisy.	Clean and replace heatsink compound.	□ Passed □ Failed		
9.	Remove A4 Moo heatsink compo	dule, Assembly, High Voltage Module. Clean and replace und.	Clean and replace heatsink compound.	□ Passed □ Failed		
10	Remove A6 Moo Clean and repla	dule ASSEMBLY, CIRCUIT CARD, FAN POWER, CCA. ce heatsink compound.	Clean and replace heatsink compound.	□ Passed □ Failed		
11.	Remove V2 ASS heatsink compo	SEMBLY, TWT, 750W,X-BAND. Clean and replace und.	Clean and replace heatsink compound.	Passed      Failed		
12.	Replace Backup	Battery and set up data properly on uP/LOGIC Controller.	ОК	Passed      Failed		
13	Check Main and	Boot Versions	Boot version:			

PROCEDURE / REPORT OF TEST №:1.2.1.1							
TEST NAME: Adv	HPA 750W PMI anced	ELEI	MENT UNDER TEST: Transmission T	X Sub System		PROJECT: TSGT-DSO	
				Main V	'ersion		
14.	Calibrate output	Voltage of the Power f	actor Module @ fully loaded	375	VDC		
15.	Calibrate TWT H	leater Voltage		6.3	3V		
16.	Calibrate Helix V	/oltage against TWT op	perational specs.	As specified of	on TWT label		
17.	Log Collector 1	Voltage		As specified of	on TWT label		
18.	Log Collector 2	Voltage		As specified of	on TWT label		
19.	Log Helix Currer	nt @500 Watt RF trans	mission	As Re	quired		
20.	Calibrate RF Forward Power			As Required			
21.	Calibrate RF rev	erse Power		As Required			
22.	Log print screen	of the HPA configurati	on pages				
General Configuration Engineering CIF         RF Power         Attenuation Set         0.08         0.08         Attenuation Set         0.07         0.07         Manual Set         0.07         0.07         1.00         0.07         1.00         0.07         1.00         0.07         1.00         0.07         1.00         0.07         1.00         0.07         1.00         1.00         0.01         1.00         0.02         0.03         1.00         0.04         1.00         1.00         0.01         1.00         1.00         1.00         1.00         0.00         0.00         0.00         0.00         0.00         0.00         0.00         0.00         0.00         0.00         0.00         0.00		eff Amp 5 (Addr 48) - 750WNC Settings         General Configuration       Engineering       CIF         Time       Minute:       Second:         Hour:       17       16       Config         Month:       Day:       Year:       Standby Elapsed:       Transmit Elapsed:         Jondon:01:36:43       J0000.05:56:33       Amptin       Amptin         Unit On Elapsed:       J0000.05:56:33       Amptin         Relay:       Relay:       BUC       Bully:         Relay:       SUM FAULT       SUM FAULT       BUC         Close       Close       Close	ystem uration: Amplifier: al dent e i dent e i dent  Unlock: Type: 	Amp 5 (Addr 48) - i General Configuration Er Cinesaizer Am Phase: Phase: Phase Magnitude: Mag	//SofWAC Settings         ogineering)       OF         Software Version:       Boot Version:         0ffset       02 00.06         is offset       01.00.36         is offset       Settings         initide Offset       Settings         initide Offset       Settings         initide Offset       Settings         initide Offset       Settings         Execute       Close		
23.	Apply other calib	pration procedures for u	IP/LOGIC Controller	As Re	quired	Passed D Failed	
24.	Apply Single Fre	equency Power & gain t	ests.	Provide te	est results	Passed      Failed	





	PROCEDURE / REPORT OF TEST Nº:1.2.1.1						
TEST NAME: Adv	: HPA 750W PMI /anced	ELEMEN	TUNDER TEST: Transmission T	X Sub System	PROJECT: TSGT-DSO		
			Amp 3 (Addr 48) - 750WNC           Edit         Vew         FF Dutput:           REMOTE         State:         FF Dutput:           Reflected RF         Stow         Normality           Weild         Stow         Normality         Reflected RF           Mark         Stow         Stow         Stow         Stow           Mark         Stow         Stow         Stow         Stow           Mark         Stow         Stow         Stow         Stow         Stow           Mark         Stow         Stow         Stow         Stow         Stow         Stow           Mark         Stow         Stow         Stow         Stow         Stow         Stow	Power Mode: MANUAL : 1W : 1W : 2mA : 2mA : 25mA : 25mA : 25mA : 25mA : 100C : 100C : 100C : 100C : 100C			
27.	Uninstall HPA #	B from its location and apply	y operational bench check.	Initial performance test.	Passed      Failed		
28.	Remove and Cle	an Fan unit B1		ОК	Passed      Failed		
29.	29. Check operation and the Replace B1 Fan unit. Replace fan after 50.000 Hours of operation or every 4 years			ОК	Passed  Failed		
30. Check operation and the Replace B2 internal Fan. Replace fan after 50.000 Hours of operation or every 4 years		ОК	Passed  Failed				
31.	Place a fan repla	cement date sticker inside t	the fan unit.	ОК	Passed      Failed		
32.	Remove A1 Asse compound.	embly, 'Power Factor Modul	e'. Clean and replace heatsink	Clean and replace heatsink compound.	Passed Failed		
33.	Remove A2 Mod heatsink compou	lule, Assembly, Power Proce	essor, CCA, Clean and replace	Clean and replace heatsink compound.	□ Passed □ Failed		

	PROCEDURE / REPORT OF TEST №:1.2.1.1						
TEST NAME Ad	: HPA 750W PMI wanced	ELEMENT UNDER TEST: Transmission TX Sub System		PROJECT: TSGT-DSO			
34.	Remove A4 Mod C1&C2when unit	ule, Assembly, High Voltage Module. Replace Capacitors i is noisy.	Clean and replace heatsink compound.	Passed      Failed			
35.	Remove A4 Mod heatsink compou	ule, Assembly, High Voltage Module. Clean and replace Ind.	Clean and replace heatsink compound.	□ Passed □ Failed			
36.	Remove A6 Mod Clean and replac	ule ASSEMBLY, CIRCUIT CARD, FAN POWER, CCA. e heatsink compound.	Clean and replace heatsink compound.	□ Passed □ Failed			
37.	Remove V2 ASSEMBLY, TWT, 750W,X-BAND. Clean and replace heatsink compound.		Clean and replace heatsink compound.	□ Passed □ Failed			
38.	Replace Backup Battery and set up data properly on uP/LOGIC Controller.		ОК	Passed      Failed			
20	Check Main and Boot Versions		Boot version:				
			Main Version				
40.	Calibrate output	Voltage of the Power factor Module @ fully loaded	375 VDC				
41.	Calibrate TWT H	eater Voltage	6.3V				
42.	Calibrate Helix V	oltage against TWT operational specs.	As specified on TWT label				
43.	Log Collector 1 \	/oltage	As specified on TWT label				
44.	Log Collector 2 \	/oltage	As specified on TWT label				
45.	Log Helix Curren	t @500 Watt RF transmission	As Required				
46.	Calibrate RF For	ward Power	As Required				
47.	Calibrate RF rev	erse Power	As Required				
48.	Log print screen	of the HPA configuration pages					

PROCEDURE / REPORT OF TEST Nº:1.2.1.1						
TEST NAME: Adv	HPA 750W PMI ELEI	X Sub System	PROJECT: TSGT-DSO			
Sere PF	Image: Second registration       Engineering       CLF         Image: Second registration       Engineering       CLF         Image: Second registration       Faults       Alams         Image: Second registration       Faults       Intervalue         Image: Second registration       Intervalue       Intervalue         Image: Second registration       Interva			) - 750WNC Settings		
49.	Apply other calibration procedures for u	IP/LOGIC Controller	As Required	Passed  Failed		
50.	Apply Single Frequency Power & gain t	tests.	Provide test results	Passed      Failed		





PROCEDURE / REPORT OF TEST №:1.2.1.1							
TEST NAME: HPA 750W PMI Advanced	ELEMENT UNDER TEST: Transmission TX Sub System	PROJECT: TSGT-DSO					
	Edit       Vew       RF Output:       Power Mode:         REMOTE       TRANSMIT       500W       MANUAL         RF Output:       500W       MANUAL         0.0       1       500W       100W         Attenuation:       0.0       0.0       0.0         0.0       1       15.0       10.99KV         0.0       1       7.50K/       15.00K         0.0       1       10.99KV       Cabinet Temp:       31C         0.0       1       10.0       50C       1       10C         0.0       1       6.0/       12.0/       25C       100C         0.0       1       50/       12.0/       50C       1       0.0         0.0       1       6.0/       12.0/       75C       20C       20C         0.0       1       50						

#### 1.2.2 TX RF OUTPUT FREQUENCY ACCURACY

PROCEDURE / REPORT OF TEST № 1.2.2								
TEST NAME: RF Output Frequency accuracy		ELEMENT UNDER TEST: Transmission Subsystem		PROJECT: TSGT-DSO				
STEP		TEST SEQUENCE	EXPECTED RESULT	RESULT	REMARKS			
1.	-Connect <b>Frequency Counter</b> to the <b>Net Cock (A</b> ), RF out BNC port, and measure the <b>10 MHz Output Frequency</b> .		10.000.000Hz ±3 Hz	Hz				

PROCEDURE / REPORT OF TEST Nº 1.2.2						
TEST NAME: RF Output Frequency accuracy		ELEMENT UNDER TEST: Transmissior	n Subsystem	PROJECT: TSGT-DSO		
2.	Connect <b>Power Meter</b> or Spectrum Analyzer to the <b>Net Cock (A</b> ), RF out BNC port, and measure the <b>10 MHz Output Level</b> .		NET CLOCK:9383 +10dBm(±1dBm)			
			NET CLOCK:9400 +13dbm (±1dBm)	dbm		
3.	- Connect <b>Powe</b> Distribution An Output Level.	e <b>r Meter</b> or Spectrum Analyzer to the Spectracom nplifier (A), RF out BNC port, and measure the 10 MHz	DIST.AMP OUTPUT NETCLOCK is 9383) (+0dbm ±1dbm) NETCLOCK is 9400 (+4dbm ±1dbm)	dbm		
4.	-Connect Freque measure the 10	ency Counter to the Net Cock (B), RF out BNC port, and MHz Output Frequency.	10.000.000Hz ±3 Hz	Hz		

		PROCEDURE / REPORT O	F TEST № 1.2.2		
TEST NAME: RF Output Frequency accuracy		ELEMENT UNDER TEST: Transmissio	n Subsystem	PROJECT: TSGT-DSO	
5.	Connect Power Meter or Spectrum Analyzer to the Net Cock (B), RF out BNC port, and measure the 10 MHz Output Level.		NET CLOCK:9383 +10dBm(±1dBm) NET CLOCK:9400 +13dbm (±1dBm)	dbm	
6.	Connect Power Meter or Spectrum Analyzer to the Spectracom Distribution Amplifier (B), RF out BNC port, and measure the 10 MHz Output Level.		DIST.AMP OUTPUT NETCLOCK is 9383 (+0dbm ±1dbm) NETCLOCK is 9400 (+4dbm ±1dbm)	+4.80dbm	
7.	Configure Test s CSSC/SATCON TX_RF_OUTPU For T1, Connect Make sure that t Signal Gen: CW P/P, L Band, U I	Setup as indicated in <b>test procedure</b> IT_ACCURACY Test Procedure" It the Frequency Counter to the port J26 of the UPLINK P/P. Sche TX subsystem output is connected to Dummy LOAD. 7, 950Mhz, 1200Mhz, 1450Mhz injected -10dbm on UPLINK Schwere the EBEM1 connected.		☐ Passed	

	PROCEDURE / REPORT OF TEST № 1.2.2						
TEST NAN Frequenc	IE: RF Output cy accuracy	ELEMENT UNDER TEST: Transmissior	n Subsystem	PROJECT: TSGT-DSO			
8.	<u>Select T1, BUC</u> Read and Fill in	A, ONLINE. the table, test results for T1 BUC A	7.90*10 <sup>9</sup> ± 285.25 Hz 8.15*10 <sup>9</sup> ± 285.25 Hz 8.40*10 <sup>9</sup> ± 285.25 Hz				
9.	Select T1, BUC	B, ONLINE. the table, test results for T1 BUC B	7.90*10 <sup>9</sup> ± 285.25 Hz 8.15*10 <sup>9</sup> ± 285.25 Hz 8.40*10 <sup>9</sup> ± 285.25 Hz				
10.	For T2, Connect Make sure that t Signal Gen: CW P/P, L Band, U I <u>Select T2, BUC</u> Read and Fill in	the Frequency Counter to the port J22 of the UPLINK P/P. he TX subsystem output is connect to Dummy LOAD. , 950Mhz, 1200Mhz, 1450Mhz injected -10dbm on UPLINK ink, where the EBEM1 connected. <u>A, ONLINE</u> . the table, test results for T2 BUC A	7.90*10 <sup>9</sup> ± 285.25 Hz 8.15*10 <sup>9</sup> ± 285.25 Hz 8.40*10 <sup>9</sup> ± 285.25 Hz				
11.	Select T2, BUC	B, ONLINE. the table test results for T2 BUC B	7.90*10 <sup>9</sup> ± 285.25 Hz 8.15*10 <sup>9</sup> ± 285.25 Hz 8.40*10 <sup>9</sup> ± 285.25 Hz				

	PROCEDURE / REPORT OF TEST Nº 1.2.2						
TEST NAM Frequenc	IE: RF Output cy accuracy	ELEMENT UNDER TEST: Transmission	n Subsystem	PROJECT: TSGT-DSO			
12.	-Switch on TFRS, reference to system. Measure the signal frequency of the signal converted to X-band. if required, adjust the frequency adjustment trimmer located on top of the BUC A and Fill in the table test results for T1 BUC A (Using Internal Frequency and front LED is YELLOW)		7.90*10 <sup>9</sup> ± 1630 Hz 8.15*10 <sup>9</sup> ± 1630 Hz 8.40*10 <sup>9</sup> ± 1630 Hz				
13.	-Switch off TFRS, reference to system. Measure the signal frequency of the signal converted to X-band. if required, adjust the frequency adjustment trimmer located on top of the BUC B and Fill in the table test results for T1 BUC B(Using Internal Frequency and front LED is YELLOW)		7.90*10 <sup>9</sup> ± 1630 Hz 8.15*10 <sup>9</sup> ± 1630 Hz 8.40*10 <sup>9</sup> ± 1630 Hz				
14.	-Switch off TFRS, reference to system. Measure the signal frequency of the signal converted to X-band. if required, adjust the frequency adjustment trimmer located on top of the BUC A and Fill in the table test results for T2 BUC A (Using Internal Frequency and front LED is YELLOW)		7.90*10 <sup>9</sup> ± 1630 Hz 8.15*10 <sup>9</sup> ± 1630 Hz 8.40*10 <sup>9</sup> ± 1630 Hz				
15.	-Switch off TFRS signal converted trimmer located BUC B (Using Ir	S, reference to system. Measure the signal frequency of the I to X-band. if required, adjust the frequency adjustment on top of the BUC B and Fill in the table test results for T2 Iternal Frequency and front LED is YELLOW)	7.90*10 <sup>9</sup> ± 1630 Hz 8.15*10 <sup>9</sup> ± 1630 Hz 8.40*10 <sup>9</sup> ± 1630 Hz				
## 1.2.3 TX MANUAL REDUNDANCY

	PROCEDURE / REPORT OF TEST Nº 1.2.3							
TEST NAME: Manual Redundancy		ELEMENT UNDER TEST: Transmissio	n Subsystem	PROJECT: TSGT-DSO				
STEP		TEST SEQUENCE	EXPECTED RESULT	RESULT	REMARKS			
1.	Configure Test s CSSC/SATCON TX_RF_OUTPU	eetup as indicated in <b>test procedure</b> I T_ACCURACY Test Procedure"						
2.	For T1, Set RSU so that BUC A is ON LINE, and establish AUTO Switchover Mode. Simulate a failure in UP Converter A by means of POWER OFF. Check that Up Converter B is ON LINE.			☐ Passed ☐ Failed				
3.	-Power on Up Converter A. Set RSU so that Up-converter B is ON LINE, and establish AUTO Switchover Mode. Simulate a failure in UP Converter B by means of POWER OFF. Check that Up Converter A is ON LINE.			Passed Failed				
4.	For T2, Set RSU so that BUC A is ON LINE, and establish AUTO Switchover Mode. Simulate a failure in UP Converter A by means of POWER OFF. Check that Up Converter B is ON LINE.			☐ Passed ☐ Failed				
5.	-Power on Up Converter A. Set RSU so that Up-converter B is ON LINE, and establish AUTO Switchover Mode. Simulate a failure in UP Converter B by means of POWER OFF. Check that Up Converter A is ON LINE.			Passed      Failed				

## 1.2.4 RX L-BAND FREQUENCY OUTPUT ACCURACY

	PROCEDURE / REPORT OF TEST Nº 1.2.4						
TEST NAM acc	<b>/E:</b> IF Output curacy	ELEMENT UNDER TEST: Reception S	ubsystem	PROJECT: TSGT-DSO			
STEP		TEST SEQUENCE	EXPECTED RESULT	RESULT	REMARKS		
1.	Configure Test setup as indicated in <b>test procedure</b> CSSC/SATCOM RX_RF_IFOUTPUT_ACCURACY Test Procedure" Signal Gen: CW, 7.25Ghz, 7.5Ghz, 7.75Ghz injected -20dbm on RX IN COUPLER, first for T1 and then T2 in turn. Connect Frequency Counter on DOWNLINK P/P, L Band, U link, where the EBEM1 connected. J40 for T2, J76 for T1.			☐ Passed ☐ Failed			
2.	<u>Select T1, BDC</u> Measure the free	<u>Select T1, BDC A, ON LINE</u> . Measure the frequency of the signal converted to L-band.					
3.	Select T1, BDC Measure the free	<u>Select T1, BDC B, ON LINE</u> . Measure the frequency of the signal converted to L-band.					
4.	Select T2, BDC Measure the free	A, ON LINE. quency of the signal converted to L-band.	950*10 <sup>6</sup> ± 33.25 Hz 1200*10 <sup>6</sup> ± 42 Hz				

PROCEDURE / REPORT OF TEST № 1.2.4							
TEST NAM acc	<b>IE:</b> IF Output uracy	ELEMENT UNDER TEST: Reception S	ubsystem	PROJECT: TSGT-DSO			
			1450*10 <sup>6</sup> ± 50.75 Hz				
5.	Select T2 BDC B, ON LINE. Measure the frequency of the signal converted to L-band.		950*10 <sup>6</sup> ± 33.25 Hz 1200*10 <sup>6</sup> ± 42 Hz 1450*10 <sup>6</sup> ± 50.75 Hz				
6.	Switch OFF the TFRS, (Distribution AMP) Select T1 Block Down-Converter A, ON LINE. Measure the frequency of the signal converted to L-band. If necessary, adjust the frequency by adjusting the trimmer on top of the BDC and record test results. (Using Internal Frequency and front LED is YELLOW)		950*10 <sup>6</sup> ± 190 Hz 1200*10 <sup>6</sup> ± 240 Hz 1450*10 <sup>6</sup> ± 290 Hz				
7.	Select T1 Block Down-Converter B, ON LINE. Measure the frequency of the signal converted to L-band. If necessary, adjust the frequency by adjusting the trimmer on top of the BDC and record test results. (Using Internal Frequency and front LED is YELLOW)		950*10 <sup>6</sup> ± 190 Hz 1200*10 <sup>6</sup> ± 240 Hz 1450*10 <sup>6</sup> ± 290 Hz				
8.	Switch OFF the TFRS, (Distribution AMP) Select T2 Block Down-Converter A, ON LINE. Measure the frequency of the signal converted to L-band. If necessary, adjust the frequency by adjusting the trimmer on top of the BDC and record test results. (Using Internal Frequency and front LED is YELLOW)		950*10 <sup>6</sup> ± 190 Hz 1200*10 <sup>6</sup> ± 240 Hz 1450*10 <sup>6</sup> ± 290 Hz				
9.	Select T2 Block	Down-Converter B, ON LINE.	950*10 <sup>6</sup> ± 190 Hz 1200*10 <sup>6</sup> ± 240 Hz				

	PROCEDURE / REPORT OF TEST № 1.2.4								
TEST NAME: IF Output accuracy		ELEMENT UNDER TEST: Reception S	ELEMENT UNDER TEST: Reception Subsystem P		PROJECT: TSGT-DSO				
	Measure the free adjust the freque test results. (Usi	quency of the signal converted to L-band. If necessary, ency by adjusting the trimmer on top of the BDC and record ing Internal Frequency and front LED is YELLOW)	1450*10 <sup>6</sup> ± 290 Hz						
10.	Switch ON TFR	S, (Distribution AMP) and return to normal configuration		Passed      Failed					

### 1.2.5 RX MANUAL REDUNDANCY

	PROCEDURE / REPORT OF TEST Nº 1.2.5							
TEST NAME: RX Manual Redundancy         ELEMENT UNDER TEST: Transmission Subsystem		ystem	PROJECT: TSGT-DSO					
STEP		TEST SEQUENCE	EXPECTED RESULT	RESULT	REMARKS			
1.	Configure Test setup as indicated in <b>test procedure</b> CSSC/SATCOM RX_RF_IFOUTPUT_ACCURACY Test Procedure" Configure RSU in manual mode and select Down-converter A ON LINE			Passed  Failed				
2.	-FOR T1, Set RSU so that Down-Converter A is ON LINE, and establish AUTO Switchover Mode. Simulate a failure in Down Converter A by means of POWER OFF. Check that Down Converter B is ON LINE.			☐ Passed ☐ Failed				
3.	Power ON, Down C establish AUTO Sw	onverter A. Set RSU so that Down-converter B is ON LINE, and itchover Mode.		Passed      Failed				

	PROCEDURE / REPORT OF TEST № 1.2.5						
TEST NAME: RX Manual Redundancy		ELEMENT UNDER TEST: Transmission Subs	ELEMENT UNDER TEST: Transmission Subsystem		PROJECT: TSGT-DSO		
	Simulate a failure in Converter A is ON I	Down Converter B by means of POWER OFF. Check that Down INE					
4.	<ul> <li>4.</li> <li>FOR T2, Set RSU so that Down-Converter A is ON LINE, and establish AUTO Switchover Mode.</li> <li>Simulate a failure in Down Converter A by means of POWER OFF. Check that Down Converter B is ON LINE.</li> </ul>			☐ Passed ☐ Failed			
5.	<ul> <li>5. Power ON, Down Converter A. Set RSU so that Down-converter B is ON LINE, and establish AUTO Switchover Mode.</li> <li>Simulate a failure in Down Converter B by means of POWER OFF. Check that Down Converter A is ON LINE</li> </ul>			☐ Passed ☐ Failed			

## 1.2.6 POWER BALANCING

## 1.2.7 T2- TX POWER BALANCING AND PHASE ALIGNMENT

#### 1. Set T-2 Tx Gain to 105 dB

- 1. Verify gain of each BUC is set to 23.8 dB.
- 2. Inject a 1200 MHz CW with a level of -10 dBm at the output of EBEM Modem #1.
- 3. Adjust the Slope Equalizer attenuator to achieve a level of -19.0 dBm at the SSPA input.
- 4. Adjust the SSPA attenuators to achieve a level of +51.3 dB, at the output of each SSPA.
- 5. Adjust the Slope Equalizer attenuator to achieve a level of +51.3 dBm at the SSPA output for all SSPA/BUC combinations.



PROCEDURE / REPORT OF TEST Nº 1.2.6 &1.2.7							
TEST NAME: Balancing	T2 Power	ELEMENT UNDER TEST: TX Subs	system	PROJECT: TSGT-DSO			
STEP		TEST SEQUENCE	EXPECTED RESULT	RESULT	REMARKS		
1.	Configure Test s <b>TSGT-3G_Pow</b> Point the T-2 an	setup as indicated. erBalancing_PhaseAlignment_Procedure tenna to Elevation >60 degrees.		Passed      Failed			
2.	Perform Power I Antenna moved connected to LC <u>Equalizer Bypa</u> -Inject 1.2 GHz, 1. POWER Mete SSPA B -Adjust <b>BUC A</b> -Switchover to E -If not, Adjust t	balancing, Phase alignment and Slope adjustment. to out of Satellite region. EL: 60 degree, Or TX Output OAD. Issed. -11.5dBm CW to the L Band P/P. er Connected to the INPUT Cable of the SSPA A and then, GAIN Potentiometer to read -19dbm on the POWER Meter. BUC B he gain of the BUC A&B and label it.	SSPA A INPUT: -19dBm				
3.	Adjust <b>BUC B G</b> -lf not, Adjust t	GAIN Potentiometer to read -19dbm on the POWER meter. he gain of the BUC A&B and label it.	SSPA B INPUT: -19dbm				
4.	Set BUC'A' via S (+51dBm) @ An If not, Adjust/Se	SSPA'A' and measure the output level of the SSPA ntenna Output Coupler t SSPA A Attenuator to read +51dbm on the Power meter.	+51dBm				
5.	Set BUC'A' via S (+51dBm) @ An If not, Adjust/Se	SSPA'B' and measure the output level of the SSPA ntenna Output Coupler t SSPA B Attenuator to read +51dbm on the Power meter.	+51dBm				

PROCEDURE / REPORT OF TEST № 1.2.6 &1.2.7								
TEST NAME: Balancing	T2 Power		FEST: TX Subs	system	PROJECT: TSGT-DSO			
6.	-Set BUC'A' via SSPA'A and B' COMBINED to the LOAD, measure the output level of the Both SSPA (+54dBm) @ Antenna Output Coupler -Adjust Phase Combiner until you see maximum peak for +54dbm on the Power meter.			+54dBm (Power doubled and 3db increased)				
7.	Set BUC'B' via (+51dBm) @ Ar	SSPA'A' and measure the output level of the second structure of the second second second second second second s	SSPA	+51dBm				
8.	Set BUC'B' via (+51dBm) @ Ar	SSPA'B' and measure the output level of the second structure of the second second second second second second s	SSPA	+51dBm				
9.	-Set BUC'B' via SSPA'A and B' COMBINED to the LOAD, measure the output level of the Both SSPA (+54dBm) @ Antenna Output Coupler.			+54dBm (Power doubled and 3db increased)				
10.	Record Attenua SSPA #A	tor set up on both SSPA's and DO NOT play/c	change them.	Attenuator final Value				
11.	Record Attenua SSPA #A	tor set up on both SSPA's and DO NOT play/c	change them.	Attenuator final Value				
12.	Capture Picture	A (dB) 5.8 RF Status Unmuted Present RF level (dBm) 38.4	ttenuation.	Connected] General a ms Others level (dB) 4.8 RF Status level (dB) 4.8 Present RF level (r	larm Normal			

	PROCEDURE / REPORT OF TEST Nº 1.2.6 &1.2.7							
<b>TEST NAME:</b> Balancing	T2 Power	ELEMENT UNDER TEST: TX Subs	system	PROJECT: TSGT-DSO				
Set Equalizer		in CIRCUIT and Change T2 Attenuator Settings in the	OUTPUT:					
13.	Equalizer to get	below readings @ Antenna Output Coupler.	+51dbm					
14.	-Select BUC A + SSPA A Adjust/Change the Preset Attenuator value SSPA A to read +51dBm output power on the Power Meter.		+51dbm					
15.	Select BUC A + SSPA B Adjust/Change the Preset Attenuator value SSPA A to read +51dBm output power on the Power Meter.		+51dbm					
16.	Select BUC A + SSPA A&B COMBINED Adjust/Change the Preset Attenuator value to read +51dBm output power on the Power Meter.		+51dbm					
17.	Select BUC B + Adjust/Change t power on the Po	- SSPA A he Preset Attenuator value SSPA A to read +51dBm output ower Meter.	+51dbm					
18.	-Select BUC B Adjust/Change t power on the Pc	<b>+ SSPA B</b> he Preset Attenuator value SSPA A to read +51dBm output ower Meter.	+51dbm					
19.	-Select BUC B + SSPA A&B COMBINED Adjust/Change the Preset Attenuator value to read +51dBm output power on the Power Meter.		+51dbm					
20.	Transmit with SSPA, 'A' only, 'B' only and COMBINED. Record the EIRP as reported by MACS			Passed D Failed				
21.	SSPA 'A' 51dbm	n out+44dbm Ant. Gain=95dbm-30db=65.0dBW	65.0dbw					

	PROCEDURE / REPORT OF TEST Nº 1.2.6 &1.2.7							
TEST NAME: Balancing	: T2 Power		ELEMENT UNDER TEST: TX Sub:	system	PROJECT: TSGT-DSO			
22.	SSPA 'B' 51dbn	n out+44dbm Ant. Ga	ain=95dbm-30db=65.0dBW	65.0dbw				
23.	Combined SSP	Combined SSPAs 65.0dBW		65.0dbw				
24.	Stick a new label (current Date) above the adjustment trimmer on both BUCs after calibration.				Passed  Failed			
25.	Save and Print screen Pre-set Equalizer Attenuator final values. For T2				□ Passed □ Failed			
			Equ. settings (connected) Equ. settings T1 path T2 path BUC A SSPA A Slope (dB) -2.5 att (dB) 15.5 SSPA B Slope (dB) -2.1 att (dB) 15.5 SSPA B Slope (dB) -2.1 SSPA B Slope (dB) -2.1 SLOPE	3)       -2.5         3)       -2.5         15.8       slope (dB)         att (dB)       18.5         3)       -2.0         3)       -2.0         16.5       att (dB)         19.0				

#### 3. Set T-1 Tx Gain to 105 dB

- 1. Verify gain of each BUC is set to 23.8 dB.
- 2. Inject a 1200 MHz CW with a level of -10 dBm at the output of EBEM Modem #1
- 3. Adjust the Slope Equalizer attenuator to achieve a level of +1.9 dBm at T-1 Extension ETB J1. (When No trailer present)
- 4. Adjust the Slope Equalizer attenuator to achieve a level of -19.0 dBm at the HPA input.
- 5. Adjust the HPA attenuators to achieve a level of +45.0 dBm, at the output of each HPA.
- 6. Adjust the Slope Equalizer attenuator to achieve a level of +45 dBm at the HPA output for all HPA/BUC combinations.



## **1.3.3.2 T1-TX POWER BALANCING AND PHASE ALIGNMENT**

PROCEDURE / REPORT OF TEST Nº 1.3.3.1 &1.3.3.2						
TEST NAME: Balancing	T1 Power	ELEMENT UNDER TEST: TX Sub	system PROJECT: TSGT-DSO			
STEP		TEST SEQUENCE	EXPECTED RESULT	RESULT	REMARKS	
1.	Configure Test setup as indicated. <b>TSGT-3G_PowerBalancing_PhaseAlignment_Procedure</b> <b>3G_PowerBalancing_PhaseAlignment_Procedure</b> Point the T-1 antenna to Elevation >60 degrees.			☐ Passed ☐ Failed		
2.	Perform Power I Antenna moved connected to LC - <u>Equalizer Byp</u> -Inject 1.2 GHz, 1. POWER Mete HPA B -Adjust <b>BUC A</b> Meter. -Switchover to E If not, Adjust	balancing, Phase alignment and Slope adjustment. to out of Satellite region. EL: 60 degree, Or TX Output OAD. -11.5 dBm CW to the L Band P/P. er Connected to the INPUT Cable of the HPA A and then, <b>GAIN</b> Potentiometer to read -19dbm on the POWER BUC B <b>the gain of the BUC A&amp;B and label it.</b>	T1 HPA A: -19dBm			
3.	Adjust <b>BUC B G</b> -If not, Adjust t	GAIN Potentiometer to read -19dbm on the POWER meter. he gain of the BUC A&B and label it.	T1 HPA B: -19dBm			
4.	Set BUC'A' via I (+45dBm) @ An If not, Adjust/Se	HPA'A' and measure the output level of the HPA htenna Output Coupler t HPA A Attenuator to read +45dbm on the Power meter.	+45dBm			
5.	Set BUC'A' via I (+45dBm) @ An If not, Adjust/Se	HPA'B' and measure the output level of the HPA Intenna Output Coupler t HPA B Attenuator to read +45dbm on the Power meter.	+45dBm			

	PROCEDURE / REPORT OF TEST № 1.3.3.1 &1.3.3.2							
TEST NAME: Balancing	T1 Power	ELEMENT UNDER TEST: TX Sub	system	PROJECT: TSGT-DSO				
6.	-Set BUC'A' via HPA 'A and B' COMBINED to the LOAD, measure the output level of the Both HPA (+48dBm) @ Antenna Output Coupler -Adjust Phase Combiner until you see maximum peak for +48dbm on the Power meter.		+48dBm (Power doubled and 3db increased)					
7.	-Set BUC'B' via HPA'A' and measure the output level of the HPA (+45dBm) @ Antenna Output Coupler		+45dBm					
8.	-Set BUC'B' via HPA'B' and measure the output level of the HPA (+45dBm) @ Antenna Output Coupler		+45dBm					
9.	-Set BUC'B' via HPA A and B COMBINED to the LOAD, measure the output level of the Both HPA (+48dBm) @ Antenna Output Coupler.		+48dBm (Power doubled and 3db increased)					
10.	Record Attenuator set up on both HPA's and DO NOT play/change them. HPA #A		Attenuator final Value					
11.	Record Attenuator set up on both HPA's and DO NOT play/change them. HPA #B		Attenuator final Value					
Capture Pictur	res print screens c	on ASNMC GUI: HPA A&B Attenuation.						
10.	Set Equalizer in CIRCUIT and Change T1 Attenuator Settings in the Equalizer to get below readings @ Antenna Output Coupler.							
11.	-Select BUC A + HPA A Adjust/Change the Preset Attenuator value HPA A to read +45dBm output power on the Power Meter.		+45dbm					
12.	-Select BUC A	+ HPA B	+45dbm					

PROCEDURE / REPORT OF TEST № 1.3.3.1 &1.3.3.2					
<b>TEST NAME:</b> Balancing	T1 Power	ELEMENT UNDER TEST: TX Sub	system	PROJECT: TSGT-DSO	
	Adjust/Change t power on the Po	he Preset Attenuator value HPA B to read +45dBm output over Meter.			
13,	-Select BUC A + HPA A&B COMBINED Adjust/Change the Preset Attenuator value to read +45dBm output power on the Power Meter.		+45dbm		
14.	-Select BUC B + HPA A Adjust/Change the Preset Attenuator value HPA A to read +45dBm output power on the Power Meter.		+45dbm		
15.	-Select BUC B + HPA B Adjust/Change the Preset Attenuator value HPA A to read +45dBm output power on the Power Meter.		+45dbm		
16.	-Select BUC B + HPA A&B COMBINED Adjust/Change the Preset Attenuator value to read +45dBm output power on the Power Meter.		+45dbm		
17.	Check that the reading on the Block Diagram EIRP matches with the All measurement. Radiate with HPA, 'A'. Record the EIRP as reported by MACS. HPA 'A' 45dbm out+50dbm Ant. Gain=95dbm-30db=65.0dBW		65dbw		
18.	Check that the reading on the Block Diagram EIRP matches with the All measurement. Radiate with HPA, 'B'. Record the EIRP as reported by MACS. HPA 'B' 45dbm out+50dbm Ant. Gain=95dbm-30db=65.0dBW		65dbw		

PROCEDURE / REPORT OF TEST Nº 1.3.3.1 &1.3.3.2						
TEST NAME: Balancing	: T1 Power	ELEMENT UNDER TEST: TX Sub	osystem	PROJECT: TSGT-DSO		
19.	Check that the r measurement. Radiate with HP Record the EIRI Combined HPA	eading on the Block Diagram EIRP matches with the All PA, COMBINED. P as reported by MACS. s 65.0dBW	65dbw			
20.	Stick a new labe BUC's after calil	el (Current Date) above the adjustment trimmer on both bration.		□ Passed □ Failed		
21.	Save and Prints HPA's GUI	screen Pre-set Equalizer Att. final set up on the ASNMC		☐ Passed ☐ Failed		
		Equ. settings         Equ. settings         T1 path       T2 path         BUC A       TWTA A         Slope (dB)       -4.6         att (dB)       15.5         BUC B       TWTA A         Slope (dB)       -4.0         Slope (dB)       -4.0         att (dB)       15.0         TWTA A       Slope (dB)       -5.2         att (dB)       16.0       att (dB)       16.0	TWTA A + TWT         slope (dB)         -5.1         att (dB)         18.4			

## 1.3.4 TX FREQUENCY RESPONSE FLATNESS TEST IN THE WHOLE BAND

PROCEDURE / REPORT OF TEST № 1.3.4							
TEST NAME: Frequency Response flatness test in the whole Band T2 &T1		ELEMENT UNDER TEST: Transmission Subsystem		PROJECT: TSGT-DSO			
STEP		TEST SEQUENCE	EXPECTED RESULT	RESULT	REMARKS		
	Prepare set up a	as indicated on the Test procedure,					
	20151108-NU-T	SGT-3G_PowerBalancing_PhaseAlignment_Procedure					
1.	Set T2 Antenna satellite.	and T2 Presets and point the antenna away from any					
	Adjust/Change S	Slope values to get a good picture.					
	Apply Procedure/test for the below combinations and record and print test results						
2.	BUC-A > SSPA	A –A	Save the trace as a JPEG file. Note the SSPA attenuator value.	Passed D Failed			













	Set T1 Antenna and T1 Presets and point the antenna away from any satellite. (OLUX matched with OLTX)		
9.	T1 BUC-A > HPA - A	Save the trace as a JPEG file. Note the HPA attenuator value	Passed D Failed
10	T1 BUC-A > HPA - B	Save the trace as a JPEG file. Note the HPA attenuator value	Passed  Failed
11.	T1 BUC-A > HPA A+B COMBINED	Save the trace as a JPEG file. Note the HPA attenuator value	Passed  Failed
12.	T1 BUC-B > HPA- A	Save the trace as a JPEG file. Note the HPA attenuator value	Passed  Failed
			· · · ·
13.	T1 BUC-B > HPA –B	Save the trace as a JPEG file. Note the HPA attenuator value	Passed  Failed
14.	T1 BUC-B > HPA A+B COMBINED	Save the trace as a JPEG file. Note the HPA Attenuator value	Passed  Failed
		·	· · · · ·

### **1.3.5 TX Spurious Test**



	PROCEDURE / REPORT OF TEST Nº 1.3.5						
TEST NAME: TX Spurious         ELEMENT UNDER TEST: Transmission S			n Subsystem	PROJECT: TSGT-DSO			
2.	Select Up-conve Find and measu Find the relative spurious that ap	erter T2 A on-line and SSPA A + B on line. ure the spurious level. Record the results on the form. e dBc between the fundamental carrier and the maximum opears. Record the results	Take note of the power required at modem output. Record the results on the form.	☐ Passed ☐ Failed			
3.	Select Up-converter T2 B on-line and SSPA A + B on line. Find and measure the spurious level. Record the results on the form. Find the relative dBc between the fundamental carrier and the maximum spurious that appears. Record the results		Take note of the power required at modem output. Record the results on the form.	☐ Passed ☐ Failed			
4.	Configure Test s Connect the spe at RF Mon & Te	setup as indicated in <b>test procedure 'SPURIORS''</b> ectrum analyser to test point T1 DC1 or FWD PWR Sample est Patch Panel.					
5.	Select Up-conve Find and measu Find the relative spurious that ap	erter T1 A and TWTA A + B on line. ure the spurious level. Record the results on the form. e dBc between the fundamental carrier and the maximum opears. Record the results	Take note of the power required at modem output. Record the results on the form.	☐ Passed ☐ Failed			
6.	Select Up-conve Find and measu Find the relative spurious that ap	erter T1 B and TWTA A + B on line. ure the spurious level. Record the results on the form. e dBc between the fundamental carrier and the maximum opears. Record the results	Take note of the power required at modem output. Record the results on the form.	☐ Passed ☐ Failed			

Independent spurious (freque	ncy (MHz) and power level (dBm))	T2 BUC-A SSPA A+B	T2 BUC-B SSPA A+B	T1 BUC-A HPA A+B	T1 BUC-B HPA A+B
TX @ 952.5 MHz					
TX @ 1200 MHz					
TX @ 1447.5 MHz					
Dependent spurious (frequend	cy (MHz) and relative power level (dBc))				
TX @ 952.5 MHz	Fundamental: Spurious:				
Tx @ 1200 MHz	Fundamental: Spurious:				
Tx @ 1447.5 MHz	Fundamental: Spurious:				
Spurious inside 2 MHz BW cer	ntred around carrier (dBc)				
Tx @ 952.5 MHz					
Tx @ 1200 MHz					
Tx @ 1447.5 MHz					
Spurious power supply related	d (dBc)				
Tx @ 952.5 MHz					
Tx @ 1200 MHz					
Tx @ 1447.5 MHz					

#### 1.3 RX SUBSYSTEM

### 1.3.1 <u>RX GAIN</u>

### 1.3.1.1 T2- RX RECEIVE CHAIN LEVEL ALIGNMENT

#### 2. Set T-2 Rx Gain to 105 dB

- 1. Inject a 7500 MHz CW with a level of -62 dBm at LNA on-line inject coupler (DC4).
- 2. Adjust the gain of each BDC to achieve a level of -10 dBm at J72 of Downlink L-Band Patch Panel.
- 3. Adjust the gain of the L-Band Amplifier in the Downlink L-Band Patch Panel to achieve a level of 0 dBm the input to Modem #1.



		PROCEDURE / REPORT OF	TEST № 1.3.1.1		
TEST NAME: T2-RX Power       ELEMENT UNDER TEST: RX Subsy         Balancing       ELEMENT UNDER TEST: RX Subsy		system	PROJECT: TSGT-DSO		
STEP		TEST SEQUENCE	EXPECTED RESULT	RESULT	REMARKS
	Configure Test s	setup as indicated in <b>test procedure Depot Level</b> I			
1.	1.4.3_20170207 Point the T-2 an Make sure that the Test Panel a	Y-NU-TSGT3G_RX_Chain Calibration Itenna to Elevation of>60 degrees the Cable Loss and Coupling factors for the test points on are measured and labeled with the right values.			
2.	Set CW 7.5Ghz, Signal Generator Power output that injecting to LNA - 62.0dBm input to the coupler (50.38dbc) T2 Online LNA A IN			Passed      Failed	
3.	Set LNA A and at L Band DOW the output level	BDC A ON LINE and Connect the power meter to the J72 NLINK P/P. Measure the output of the BDC A and adjust for -10dbm (1.2Ghz)	-10dBm		
4.	Set LNA A and at L Band DOW the output level	BDC B ON LINE and Connect the power meter to the J72 NLINK P/P. Measure the output of the BDC B and adjust for -10dbm (1.2Ghz)	-10dBm		
5.	Connect the pown 1 at the Downlin Set LNA'A' via E Amplifier if requ	wer meter to the down-link splitter output connector FDMA ik Patch Panel 3DC'A', read and record the power level. Adjust the LINE ired to 0dbm.	+0.0dBm		
6.	Set LNA'A' via BDC'B', read and record the power level.		+0.0dBm		
7.	Set LNA'B' via E	BDC'A', read and record the power level.	+0.0dBm		

	PROCEDURE / REPORT OF TEST Nº 1.3.1.1							
TEST NAME: T2-RX Power Balancing		ELEMENT UNDER TEST: RX Subsystem		PROJECT: TSGT-DSO				
8.	Set LNA'B' via BDC'B', read and record the power level.		+0.0dBm					
9.	Stick a new labe BDC's after calil	el (current Date) above the adjustment trimmer on both bration.		□ Passed □ Failed				
10.	Apply Single LN	A Gain/Sweep by using ENA or PNA						
11.	T2 LNA A Gain		50dB +- 3 dB					
12.	Save LNA A Sw	reep test results as a JPEG.		☐ Passed ☐ Failed				



PROCEDURE / REPORT OF TEST Nº 1.3.1.1						
TEST NAME: Balancing	<b>T2-</b> RX Power	ELE	MENT UNDER TEST: RX SU	ıbsystem	PROJECT: TSGT-DSO	
14.	T2LNA B Gain			50 dB +- 3 dB		
15.	Save LNA B Sw	eep test results as a JPEG.			□ Passed □ Failed	
		E5071C Network Analyzer         1 Active Ch/Trace       2 Response       3 Stimulus       4 M         1 Tr1       521 Log Mag       1.000dB/ Ref       10.1         15.40       1       7.2500000 GHZ       10.2         2       7.500000 GHZ       10.4         14.40       13.40       11.40         11.40       10.40       10.40         9.400       8.400       10.40         7.400       10.40       10.40	Ikr/Analysis       5 Instr State         40d8       [F2 Sm0]         56       dB         45       dB         29       dB         40       Image: Simple state		Resize         System         Print         Invert Image         ON         Dump         Screen Image         Multiport Test Set         Setup         Misc Setup         Backlight         ON         Firmware         Revision         Service Menu         Help         Return	
		6.400 5.400 1   Start 7.25 GHz	IFBW 70 kHz	Stop 7.75 GHz 16/16 C Meas Stop ExtRef S	vc[ 2020-03-05 20:22]	

PROCEDURE / REPORT OF TEST № 1.3.1.1							
TEST NAME: T2-RX Power Balancing		ELEMENT UNDER TEST: RX Sub	ELEMENT UNDER TEST: RX Subsystem				
16.	<b>16.</b> Connect a Multimeter to the T2 LNA A test point on top of the LNA Controller, Check and Adjust POT as required. Log the result.		6.5 Volt for good LNA	☐ Passed ☐ Failed			
17.	17. Connect a Multimeter to the T2 LNA B test point on top of the LNA Controller, Check and Adjust POT as required. Log the result.		6.5 Volt for good LNA	☐ Passed ☐ Failed			

## 1.4.3.2 T1- RX RECEIVE CHAIN LEVEL MEASUREMENT

#### 4. Set T-1 Rx Gain to 105 dB

- 1. Inject a 7500 MHz CW with a level of -22.7 dBm at T-1 Extension ETB J2. (When No trailer present)
- 2. Inject a 7500 MHz CW with a level of -56 dBm at T-1 LNA DC Coupler.
- 3. Adjust the gain of each BDC to achieve a level of -10 dBm at J76 of Downlink L-Band Patch Panel.
- 4. Adjust the gain of the L-Band Amplifier in the Downlink L-Band Patch Panel to achieve a level of 0 dBm at the input to Modem #1



PROCEDURE / REPORT OF TEST Nº 1.4.3.2						
<b>TEST NAME</b> Balancing	<b>: T1</b> RX Power	ELEMENT UNDER TEST: RX Sub	system	PROJECT: TSGT-DSO		
STEP		TEST SEQUENCE	EXPECTED RESULT	RESULT	REMARKS	
	Configure Test s	setup as indicated <b>in test procedure Depot Level</b> /				
1.	TSGT3G_RX_C Point the T-1 an Make sure that t the Test Panel a	Chain Calibration Itenna to an elevation of >60 degrees (T1 is OTQX) The Cable Loss and Coupling factors for the test points on are measured and labeled with the right value.				
2.	Apply Single LN	IA Gain/Sweep by using ENA or PNA				
3.	T1LNA A Gain		50 dB +- 3 dB			
4.	Save LNA A Sw	eep test results as a JPEG.		☐ Passed ☐ Failed		
5.	Apply Single LN	IA Gain/Sweep by using ENA or PNA				
6.	T1LNA B Gain		50 dB +- 3 dB			
7.	Save LNA B Sw	eep test results as a JPEG.		Passed Failed		
8.	Calculated LNA	GAIN Difference	< 1 dB			

PROCEDURE / REPORT OF TEST Nº 1.4.3.2						
TEST NAME: Balancing	T1 RX Power	ELEMENT UNDER TEST: RX Sub	system PROJECT: TSGT-DSO			
9.	Set Signal Gene Online LNA @ F	erator Power output CW that injecting to LNA -56.0dBm T1 RF INPUT Coupler on the upper side of the LNAs.				
10.	Set LNA A and I at L Band DOW adjust the outpu	BDC A ON LINE and Connect the power meter to the J72 NLINK P/P. Measure the output of the T1 BDC A and t level for -10dbm (1.2Ghz)	-10dBm			
11.	Set LNA A and I at L Band DOW the output level	BDC B ON LINE and Connect the power meter to the J72 NLINK P/P. Measure the output of the BDC B and adjust for -10dbm (1.2Ghz)	-10dbm			
12.	Connect the power meter to the downlink, splitter output connector, FDMA 1 at the Downlink Patch Panel.					
13.	Set LNA'A' via BDC'A', read and record the power level. Adjust the T1 LINE Amplifier if required to 0dbm		+0.0dB			
14.	Set LNA'A' via E	BDC'B', read and record the power level.	+0.0dBm			
15.	Set LNA'B' via E	BDC'A', read and record the power level.	+0.0dBm			
16.	Set LNA'B' via E	BDC'B', read and record the power level.	+0.0dbm			
17.	Stick a new label (current Date) above the adjustment trimmer on both BDC's after calibration.			Passed  Failed		
18.	Connect a Multimeter to the T1 LNA A test point on top of the LNA Controller, Check and Adjust POT as required. Log the result.		6.5 Volt for good LNA	Passed Failed		
19.	Connect a Multin Controller, Chec	meter to the T1 LNA B test point on top of the LNA k and Adjust POT as required. Log the result.	6.5 Volt for good LNA	Passed I Failed		

## 1.3.2 T2 RX FREQUENCY RESPONSE IN WHOLE BAND

PROCEDURE / REPORT OF TEST Nº 1.3.2					
TEST NAME: T2 Frequency response in whole band		ELEMENT UNDER TEST: Reception Subsystem		PROJECT: TSGT-DSO	
STEP		TEST SEQUENCE	EXPECTED RESULT	RESULT	REMARKS
	Configure Test setup as indicated in test procedure			ок	
1.	CSSC/SATCOM				
		CY_RESPONSE_TEST_PROCEDURE for T2 antenna			
	setup				
	Ensure that the	antenna is not pointed on any satellite			
	Connect the Net	twork Analyzer PORT1 to LNA INPUT Coupler and PORT2			
	to the DOWNLIN	NK P/P Modem 1. U link is removed,			
	Measure the amplitude versus frequency response X-BAND to LBAND.				
2.	T2 LNA A- BDC A		<± 2 dB	□ Passed □ Failed	
			Save the trace as a JPEG		








PROCEDURE / REPORT OF TEST Nº 1.3.2									
TEST NAME response i	<b>: T2</b> Frequency n whole band	ELEMENT UNDER TEST: Reception S	Subsystem	PROJECT: TSGT-DSO					
	RX_FREQUENC	Y_RESPONSE_TEST_PROCEDURE for T1 antenna							
	setup								
	Connect the Net	work Analyzer PORT1 to LNA INPUT Coupler and PORT2							
	to the DOWNLIN	IK P/P Modem 1. U link is removed,							
	Measure the am	plitude versus frequency response X-BAND to LBAND.							
6	T1 LNA A- BDC	A	<± 2 dB	Passed      Failed					
0.			Save the trace as a JPEG						
7	T1 LNA A- BDC	В	<± 2 dB	Passed      Failed					
			Save the trace as a JPEG						
8	T1 LNA B- BDC	A	<± 2 dB	Passed      Failed					
0.			Save the trace as a JPEG						
٩	T1 LNA B- BDC	В	<± 2 dB	Passed      Failed					
5.			Save the trace as a JPEG						

#### 1.3.3 RX Spurious T1&T2



	PROCEDURE / REPORT OF TEST № 1.3.3								
TEST NAME: T2 RX Spurious		ELEMENT UNDER TEST: Reception S	ELEMENT UNDER TEST: Reception Subsystem						
3.	Select T2 LNA A Record the resu Attach interestin	and Down-converter B. on-line. Apply procedure. Its. To the specific spurious test data sheet and Plot /Save g plots showing spurious if any;	< 30dBc						
4.	Select T2 LNA E Record the resu Attach interestin	and Down-converter A. on-line. Apply procedure. Its. To the specific spurious test data sheet and Plot /Save g plots showing spurious if any;	< 30dBc						
5.	Select T2 LNA B and Down-converter Bon-line. Apply procedure. Record the results. To the specific spurious test data sheet and Plot /Save Attach interesting plots showing spurious if any;		< 30dBc						

#### Results: RX Spurious : T2 LNA A DOWN CONVERTER A

		Independent	spurious (frequency, level and R	BW)	
		Dependent sp	urious (frequency, level, RBW and	l dBc)	
Tx @ 950 MHz		Fundamental: Spurious:			
Tx @ 1200 MHz		Fundamental: Spurious:			
Tx @ 1450 MHz		Fundamental: Spurious:			
		Spurious inside	e 2 MHz BW centred around carrie	r (dBc)	
Tx @ 950 MHz					
Tx @ 1200 MHz					
Tx @ 1450 MHz					
		Spurio	ous power supply related (dBc)		
Tx @ 950 MHz					
Tx @ 1200 MHz					
Tx @ 1450 MHz					
Signal Frequency	Loss b &Tes	between RF Mon st P/P and LNA input	Signal occupied bandwidth	Signal Power level measured	Signal Power level at LNA input
FUNDAMENTAL:					
Spurious 1:					
Spurious 2:					
Spurious 3:					
Spurious 4:					

#### Results: RX Spurious : T2 LNA A DOWN CONVERTER B

		Independent	spurious (frequency, level and R	BW)	
		Dependent sp	urious (frequency, level, RBW and	l dBc)	
Tx @ 950 MHz		Fundamental: Spurious:			
Tx @ 1200 MHz		Fundamental: Spurious:			
Tx @ 1450 MHz		Fundamental: Spurious:			
		Spurious inside	e 2 MHz BW centred around carrie	r (dBc)	
Tx @ 950 MHz					
Tx @ 1200 MHz					
Tx @ 1450 MHz					
		Spurio	ous power supply related (dBc)		
Tx @ 950 MHz					
Tx @ 1200 MHz					
Tx @ 1450 MHz					
Signal Frequency	Loss b &Tes	between RF Mon st P/P and LNA input	Signal occupied bandwidth	Signal Power level measured	Signal Power level at LNA input
FUNDAMENTAL:					
Spurious 1:					
Spurious 2:					
Spurious 3:					
Spurious 4:					

#### Results: RX Spurious : T2 LNA B DOWN CONVERTER A

		Independent	spurious (frequency, level and R	BW)	
		Dependent sp	urious (frequency, level, RBW and	l dBc)	
Tx @ 950 MHz		Fundamental: Spurious:			
Tx @ 1200 MHz		Fundamental: Spurious:			
Tx @ 1450 MHz		Fundamental: Spurious:			
		Spurious inside	e 2 MHz BW centred around carrie	r (dBc)	
Tx @ 950 MHz					
Tx @ 1200 MHz					
Tx @ 1450 MHz					
		Spurio	ous power supply related (dBc)		
Tx @ 950 MHz					
Tx @ 1200 MHz					
Tx @ 1450 MHz					
Signal Frequency	Loss b &Tes	between RF Mon st P/P and LNA input	Signal occupied bandwidth	Signal Power level measured	Signal Power level at LNA input
FUNDAMENTAL:					
Spurious 1:					
Spurious 2:					
Spurious 3:					
Spurious 4:					

#### Results: RX Spurious : T2 LNA B DOWN CONVERTER B

		Independent	spurious (frequency, level and R	BW)	
		Dependent sp	urious (frequency, level, RBW and	l dBc)	
Tx @ 950 MHz		Fundamental: Spurious:			
Tx @ 1200 MHz		Fundamental: Spurious:			
Tx @ 1450 MHz		Fundamental: Spurious:			
		Spurious inside	e 2 MHz BW centred around carrie	r (dBc)	
Tx @ 950 MHz					
Tx @ 1200 MHz					
Tx @ 1450 MHz					
		Spurio	ous power supply related (dBc)		
Tx @ 950 MHz					
Tx @ 1200 MHz					
Tx @ 1450 MHz					
Signal Frequency	Loss b &Tes	between RF Mon st P/P and LNA input	Signal occupied bandwidth	Signal Power level measured	Signal Power level at LNA input
FUNDAMENTAL:					
Spurious 1:					
Spurious 2:					
Spurious 3:					
Spurious 4:					



PROCEDURE / REPORT OF TEST № 1.3.3									
TEST NAME: T1 RX Spurious		ELEMENT UNDER TEST: Reception S	PROJECT: TSGT-DSO						
	Record the resu Attach interestin	Its. To the specific spurious test data sheet and Plot /Save g plots showing spurious if any;							
4.	Select T1 LNA E Record the resu Attach interestin	B and Down-converter A. on-line. Apply procedure. Its. To the specific spurious test data sheet and Plot /Save g plots showing spurious if any;	< 30dBc						
5.	Select T1 LNA B and Down-converter Bon-line. Apply procedure. Record the results. To the specific spurious test data sheet and Plot /Save Attach interesting plots showing spurious if any;		< 30dBc						

#### Results: RX Spurious : T1 LNA A DOWN CONVERTER A

		Independent	spurious (frequency, level and R	BW)	
		Dependent sp	urious (frequency, level, RBW and	l dBc)	
Tx @ 950 MHz		Fundamental: Spurious:			
Tx @ 1200 MHz		Fundamental: Spurious:			
Tx @ 1450 MHz		Fundamental: Spurious:			
		Spurious inside	e 2 MHz BW centred around carrie	r (dBc)	
Tx @ 950 MHz					
Tx @ 1200 MHz					
Tx @ 1450 MHz					
		Spurio	ous power supply related (dBc)		
Tx @ 950 MHz					
Tx @ 1200 MHz					
Tx @ 1450 MHz					
Signal Frequency	Loss b &Tes	between RF Mon st P/P and LNA input	Signal occupied bandwidth	Signal Power level measured	Signal Power level at LNA input
FUNDAMENTAL:					
Spurious 1:					
Spurious 2:					
Spurious 3:					
Spurious 4:					

#### Results: RX Spurious : T1 LNA A DOWN CONVERTER B

		Independent	spurious (frequency, level and R	BW)	
		Dependent sp	urious (frequency, level, RBW and	l dBc)	
Tx @ 950 MHz		Fundamental: Spurious:			
Tx @ 1200 MHz		Fundamental: Spurious:			
Tx @ 1450 MHz		Fundamental: Spurious:			
		Spurious inside	e 2 MHz BW centred around carrie	r (dBc)	
Tx @ 950 MHz					
Tx @ 1200 MHz					
Tx @ 1450 MHz					
		Spurio	ous power supply related (dBc)		
Tx @ 950 MHz					
Tx @ 1200 MHz					
Tx @ 1450 MHz					
Signal Frequency	Loss b &Tes	between RF Mon st P/P and LNA input	Signal occupied bandwidth	Signal Power level measured	Signal Power level at LNA input
FUNDAMENTAL:					
Spurious 1:					
Spurious 2:					
Spurious 3:					
Spurious 4:					

#### Results: RX Spurious : T1 LNA B DOWN CONVERTER A

		Independent	spurious (frequency, level and R	BW)	
		Dependent sp	urious (frequency, level, RBW and	l dBc)	
Tx @ 950 MHz		Fundamental: Spurious:			
Tx @ 1200 MHz		Fundamental: Spurious:			
Tx @ 1450 MHz		Fundamental: Spurious:			
		Spurious inside	e 2 MHz BW centred around carrie	r (dBc)	
Tx @ 950 MHz					
Tx @ 1200 MHz					
Tx @ 1450 MHz					
		Spurio	ous power supply related (dBc)		
Tx @ 950 MHz					
Tx @ 1200 MHz					
Tx @ 1450 MHz					
Signal Frequency	Loss b &Tes	between RF Mon st P/P and LNA input	Signal occupied bandwidth	Signal Power level measured	Signal Power level at LNA input
FUNDAMENTAL:					
Spurious 1:					
Spurious 2:					
Spurious 3:					
Spurious 4:					

#### Results: RX Spurious : T1 LNA B DOWN CONVERTER B

		Independent	spurious (frequency, level and R	BW)	
		Dependent sp	urious (frequency, level, RBW and	l dBc)	
Tx @ 950 MHz		Fundamental: Spurious:			
Tx @ 1200 MHz		Fundamental: Spurious:			
Tx @ 1450 MHz		Fundamental: Spurious:			
		Spurious inside	e 2 MHz BW centred around carrie	r (dBc)	
Tx @ 950 MHz					
Tx @ 1200 MHz					
Tx @ 1450 MHz					
		Spurio	ous power supply related (dBc)		
Tx @ 950 MHz					
Tx @ 1200 MHz					
Tx @ 1450 MHz					
Signal Frequency	Loss b &Tes	between RF Mon st P/P and LNA input	Signal occupied bandwidth	Signal Power level measured	Signal Power level at LNA input
FUNDAMENTAL:					
Spurious 1:					
Spurious 2:					
Spurious 3:					
Spurious 4:					

#### **1.3.3.1** TX to RX Isolation and TX inter-modulation falling in the RX band Test



PROCEDURE / REPORT OF TEST № 1.3.3								
TEST NAME: TX to RX Isolation and TX inter- modulation falling in the RX band Test		ELEMENT UNDER TEST: Reception Subsystem		PROJECT: TSGT-DSO	PROJECT: TSGT-DSO			
1	Configure Test s and TX inter-m Connect the free Select Up-conv Select LNA A o	etup as indicated in <b>test procedure 'TX to RX Isolation</b> odulation falling in the RX band Test" uuency counter or spectrum analyser toT1 TX DC 1 erter A on-line and T1 TWTA A+B to load. n-line and Down-converter A on-line.						
2	Measure any no and RBW & VBV analyser centre Record the noise Make sure that the any obstacles, we noise floor.	n-desired signal in the whole reception band. Reduce span V accordingly. Scan the whole band by changing the frequency. If floor at 1450 MHz using Marker Noise Function. The antenna is pointed neither on a satellite nor towards which could generate inter-modulation products or increase		dBm.				
3	Connect T1 TW Record the noise Change HPA att Record the noise Provide spectrue <b>One FDMA</b> Set BW = 512 K Set BW = 2048	TA A+B to antenna by means of switch S3 e floor at 1450 MHz using Marker Noise Function. enuators if necessary up to 0 dB to get maximum power. e floor at 1450 MHz using Marker Noise Function. m analyser display plots with RF=ON and RF=OFF. <b>Carrier</b> bps. and check results Kbps. and check results	Check that the noise floor does not change by more than 0.5 dB when RF is switched ON and OFF.	dBm. dBm.				

		PROCEDURE / REPORT	OF TEST № 1.3.3		
TEST NAME: Isolation and T modulation fal band Test	TX to RX X inter- ing in the RX	LEMENT UNDER TEST: Reception S	Subsystem	PROJECT: TSGT-DSO	
	Set BW = 4096 Kbps. and check results Set BW = 8192 Kbps. and check results			dBm. dBm.	
	Switch LNA-B and Set BW = 512 Kbps. and check results Set BW = 2048 Kbps. and check results Set BW = 4096 Kbps. and check results Set BW = 8192 Kbps. and check results	· ·		dBm. dBm. dBm. dBm.	
4	Two Simultaneous Carriers Set BW at 2 FDMA carriers at 4096 Kbp Switch LNA-B and Set BW at 2 FDMA carriers at 4096 Kbp	os and check results	Check that the noise floor does not change by more than 0.5 dB when RF is switched ON and OFF.	dBm. dBm.	
5	Four Simultaneous Carriers Set BW at 4 FDMA carriers at 2048 Mb Switch LNA-B and Set BW at 4 FDMA carriers at 2048 Mb	ps and check results ps and check results	Check that the noise floor does not change by more than 0.5 dB when RF is switched ON and OFF.	dBm. dBm.	
6	Four Simultaneous Carriers Set BW at 2 FDMA carriers at 2048 Mb Set BW at 2 EPM carriers at CW / modu Switch LNA-B and	ps ulated and check results	Check that the noise floor does not change by more than 0.5 dB when RF is switched ON and OFF.	dBm.	

PROCEDURE / REPORT OF TEST Nº 1.3.3										
TEST NAME: Isolation and T modulation fal band Test	TX to RX X inter- ling in the RX	ELEMENT UNDER TEST: Reception S	PROJECT: TSGT-DSO							
	Set BW at 2 FD Set BW at 2 EP	MA carriers at 2048 Mbps M carriers at CW / modulated and check results								
	Configure Test s and TX inter-ma Connect the free	setup as indicated in <b>test procedure 'TX to RX Isolation</b> odulation falling in the RX band Test" quency counter or spectrum analyser to T2 TX DC 1								
7.	Select Up-conv Select LNA A o	rerter A on-line and T2 SSPA A+B to load. n-line and Down-converter A on-line.								
8.	Measure any no and RBW & VBV analyser centre Record the noise Make sure that t any obstacles, w noise floor.	n-desired signal in the whole reception band. Reduce span W accordingly. Scan the whole band by changing the frequency. e floor at 1450 MHz using Marker Noise Function. he antenna is pointed neither on a satellite nor towards /hich could generate inter-modulation products or increase		dBm.						
9.	Connect T1 TW Record the noise Change HPA att Record the noise Provide spectrue	TA A+B to antenna by means of switch S3 e floor at 1450 MHz using Marker Noise Function. enuators if necessary up to 0 dB to get maximum power. e floor at 1450 MHz using Marker Noise Function. m analyser display plots with RF=ON and RF=OFF.	Check that the noise floor does not change by more than 0.5 dB when RF is switched ON and OFF.							

		PROCEDURE / REPORT	T OF TEST № 1.3.3		
TEST NAME Isolation and <sup>-</sup> modulation fal band Test	: TX to RX TX inter- lling in the RX	ELEMENT UNDER TEST: Reception	Subsystem	PROJECT: TSGT-DSO	
	One FDMA         Set BW = 512 KH         Set BW = 2048 H         Set BW = 4096 H         Set BW = 8192 H         Switch LNA-B a         Set BW = 512 KH         Set BW = 2048 H         Set BW = 8192 H	Carrier ops. and check results (bps. and check results (bps. and check results (bps. and check results nd ops. and check results (bps. and check results (bps. and check results (bps. and check results		dBm. dBm. dBm. dBm. dBm. dBm. dBm.	
10.	Two Simulta Set BW at 2 FD Switch LNA-B a Set BW at 2 FD	Aneous Carriers MA carriers at 2048 Kbps and check results nd MA carriers at 2048 Kbps and check results	Check that the noise floor does not change by more than 0.5 dB when RF is switched ON and OFF.	dBm. dBm. dBm.	
11.	Set BW at 4 FD Switch LNA-B a Set BW at 4 FD	aneous Carriers MA carriers at 2048 Mbps and check results nd MA carriers at 2048 Mbps and check results	Check that the noise floor does not change by more than 0.5 dB when RF is switched ON and OFF.	dBm.	
12.	Four Simult	aneous Carriers	Check that the noise floor does not change by more	dBm.	

	PROCEDURE / REPORT OF TEST Nº 1.3.3										
TEST NAME: Isolation and T modulation fal band Test	: TX to RX IX inter- ling in the RX	ELEMENT UNDER TEST: Reception	Subsystem	PROJECT: TSGT-DSO							
	Set BW at 2 FD	MA carriers at 2048 Mbps	than 0.5 dB when RF is switched ON and OFF.								
	Set BW at 2 EP	PM carriers at CW / modulated and check results									
	Switch LNA-B a	and		dBm.							
	Set BW at 2 FD	MA carriers at 2048 Mbps									
	Set BW at 2 EP	M carriers at CW / modulated and check results									

#### 1.3.3.2 T1 &T2 PASSIVE INTERMODULATION TEST (PIM)

		PROCEDURE / REPORT	Г OF TEST № 1.3.3					
TEST NAME: Passive Inter	<b>: T1 and T2</b> modulation Test	ELEMENT UNDER TEST: Complete	e System	PROJECT: TSGT-DSO				
STEP         TEST SEQUENCE         EXPECTED RESULT         RESULT         REMARKS								



	PROCEDURE / REPORT OF TEST № 1.3.3											
TEST NAME: Passive Inter r	: <b>T1 and T</b> modulatior	r <mark>2</mark> n Test		E	ELEMENT	UNDER 1	EST: Complete	e System		PROJECT: TSGT-DSO		
	Configur	re Test set	tup as indic	ated in <b>test</b>	procedur	e Passive	Inter					
	Modulat	tion (PIM)	test"									
1.	Connect respectiv level 50	t combined ve antenn dBm outp	d Signal ger la input EBB ut for single	nerators out EM 1 T1 un e carrier for	put to the ider test ai double ca	L-BAND p nd reach T rrier 53 dE	batch panel TX power Bm.					
	on the ta	able below	n Analyser t ′.	o output of	LNA A or I	3 and reco	ord the results					
	3 <sup>rd</sup> Order Intermodulation Products(IM3)											
	F1 RF MHz	F1 RF MHz	IM3	LNA Gain	Cable loss	Xfer Gain	Measured dBm	Calculated dBm	Spec Max dBm			
	7900	8050	7750						-135.00			
2.	7900	8100	7700						-135.00	☐ Passed └ Failed		
	7900	8200	7600						-135.00			
	7900	8300	7500						-135.00			
	7900	8400	7400						-135.00			
	3 <sup>rd</sup> Orde	er Intermo	dulation P	roducts(IM	5)							
_	F1 RF MHz	F1 RF MHz	IM5	LNA Gain	Cable loss	Xfer Gain	Measured dBm	Calculated dBm	Spec Max dBm			
3.	7900	8050	7600						-135.00	Passed Failed		
	7900	8100	7500						-135.00			
	7900	8200	7300						-135.00			
	7th Ord	er Intermo	odulation F	Products(IN	17)							
4.	F1 RF MHz	F1 RF MHz	IM7	LNA Gain	Cable loss	Xfer Gain	Measured dBm	Calculated dBm	Spec Max dBm	Passed      Failed		

	PROCEDURE / REPORT OF TEST Nº 1.3.3											
TEST NAME Passive Inter	ELEMENT UNDER TEST: Complete System									PROJECT: TSGT-DSO		
	7900	8050	7450						-135.00			
	7900	8100	7300						-135.00			
5.	Worst C	ase 3 <sup>rd</sup> or	der Product	level in dB	m					dBm		
6.	Average	e 3 <sup>rd</sup> order	Product lev	el in dBm						dBm		
7.	Configu Modula Connec respecti level 50 Connec on the ta	Configure Test setup as indicated in <b>test procedure Passive Inter</b> <b>Modulation (PIM) test"</b> Connect combined Signal generators output to the L-BAND patch panel respective antenna input EBEM 1 T2 under test and reach TX power level 50 dBm output for single carrier for double carrier 53 dBm. Connect Spectrum Analyser to output of LNA A or B and record the results on the table below.										
	3 <sup>rd</sup> Orde F1 RF MHz	F1 RF MHz	IM3	roducts(IN LNA Gain	13) Cable loss	Xfer Gain	Measure dBm	d Calculat dBm	ed Spec Max dBm			
	7900	8050	7750						-135.00			
8.	7900	8100	7700						-135.00	Passed      Failed		
	7900	8200	7600						-135.00			
	7900	8300	7500						-135.00			
	7900	8400	7400						-135.00	]		
	3 <sup>rd</sup> Order Intermodulation Products(IM5)											
9.	F1 RF MHz	F1 RF MHz	IM5	LNA Gain	Cable loss	Xfer Gain	Measure dBm	d Calculat dBm	ed Spec Max dBm	Passed  Failed		

	PROCEDURE / REPORT OF TEST Nº 1.3.3											
TEST NAME: T1 and T2         ELEMENT UNDER TEST: Complete System           Passive Inter modulation Test         Element Under Test										PROJECT: TSGT-DSO		
	7900 8050 7600									-135.00		
7900 8100 7500										-135.00		
7900 8200 7300									-135.00			
	7th Ord	er Intermo	dulation P	roducts(II	M7)		-					
10.	F1 RF MHz	F1 RF MHz	IM7	LNA Gain	Cable loss	Xfer Gain	Measure dBm	ed Ca dE	alculated Bm	Spec Max dBm		
	7900	8050	7450							-135.00		
7900 8100 7300									-135.00			
11. Worst Case 3 <sup>rd</sup> order Product level in dBm											dBm	
12.	Average 3 <sup>rd</sup> order Product level in dBm										dBm	

#### 1.5 ANTENNA POSITIONING SUBSYSTEM TEST

### 1.5.1 T2- ACU and ANTENNA DRIVE SYSTEM Test Procedure

	PROCEDURE / REPORT OF TEST Nº 1.5.1												
TEST NAME: T2 Antenna         ELEMENT UNDER TEST: Antenna S           Operational checks         Image: Source of the second									Subsystem			PROJECT: TSGT-DSO	
STEP	STEP TEST SEQUENCE								EXPECTED RES	SULT	Γ	RESULT	REMARKS
	Configure antenna operation and settings according to reference procedure 600-1219 Rev B 2_4m O-M MANUAL and NCIA CSSC EMB TSS PMI procedures.												
	-			TSGT G3 T2					TSGT G3 T1				
				Up Hardware Limit 85		_			Up Hardware Limit 82				
				Up Software Limit 80					Up Hardware Limit 81	(El Mo	otor)		
				Deploy 10					Up Software Limit 80				
									Deploy 22.5				
			-153	-148	148	t 153		-70	ស៊	65	it 70		
			vare Limit	ware Limit	tware Limit	rdware Limi		ware Limit	tware Limit	ftware Limit	rdware Lim		
CCCW Hardw CCCCW Soft							CCW Hard	CCCW Sof	CW So	CW Ha			
	Down Software Limit 5								Down Software Limit	10			
	Down Hardware Limit 0								Down Hardware Limit	6.5 (E	El Mot	pr)	
	Stow HW SW Velocity EL -72(2.5 Inc) Stow CMD EL/AZ -79(281)/0								Stow HW SW Stow Ba	r raise	e -45		
					.,,				Stow HW SW Velocity Stow CMD EL/AZ -58(	EL -5 (300)/	0		



		PROCEDURE / REPORT OF 1	rest № 1.5.1	
TEST NAM Operatio	E: T2 Antenna nal checks	ELEMENT UNDER TEST: Antenna S	Subsystem	PROJECT: TSGT-DSO
3.	Check ACU/PDL	J Link		Passed      Failed
4.	Check compass	type and compass operation when SSPA's ON	True NORTH	Passed      Failed
5.	Activate DEPLO compare read ou	Y Mode antenna and check Compass heading and at against handheld Compass	Heading as required Deploy>10 deg.EL.	Passed  Failed
6.	Make sure anter 'DEPLOYED" M	nna is moving to' DEPLOY' position and giving essage	Deployed @10 Deg. EL	Passed  Failed
7.	Verify the absen Messages/Faults Read and Write Check that the "o Messages/Statu moment, the GP Check GPS Qua Read and Write Check that the c	ce of the "ACU-GPS LINK DOWN" fault message in the s screen. down the coordinates as shown in Setup/Calib screen GPS DATA UNAVAIL" message appears on the s screen. Wait until the message disappears. In this S receiver has acquired a valid site location. lity down the coordinates as shown in Setup/Calib screen oordinates are correct	Long.: Lat.:	Passed Failed Long E Lat.: N
8.	Activate STOW	Mode and check antenna stowing as required. And Check nna STOW command	Elevation Stow command -77.0	Command:
9.	Check antenna i Check AZ STOV	s center on AZ to 0 degree and fitting into the frame, V Centre switch operation.	Check AZ center Offset =0 Check Centre Switch	Offset= ☐ Passed ☐ Failed

			PROCEDURE / RE	EPORT OF	TEST № 1.5.1				
TEST NAM Operation	<b>IE:</b> T2 Antenna onal checks		ELEMENT UNDER TEST	Subsystem		PROJE	CT: TSGT-DSO		
10.	Check anten position. If no	na, slowing when anten ot, adjust the Switch loca	na reaches 5-7cm to final sto ated in the EL pedestal.	ow			🗆 Pas	sed 🗌 Failed	
11.	Check Anten	na STOWED messages	s and actual STOW position		Elevation Stow a Stowed message	actual value e	Actual Value:		
12.	Check Manu	al ACU/ Antenna JOG (	Commands				🗆 Pas	sed 🛛 Failed	
13.	Check Satell	ite Preset list availability	r for 6 satellites				🗆 Pas	sed 🗌 Failed	
14.	Activate at le tracking syst data table fo If cannot find calibration ar	east 2 different satellite s em is finding satellites. I or T2" satellites set proper He nd record the value	earches and make sure ante Record test results <b>to "Sate</b> eading offset on the compass	enna- Ilite track	Heading Offset:		Heading Offset: (Mark Angle) Passed Failed		
SATE	ILITE NAME	Satellite Inclination	Track mode	S/S Ant	enna pointed	Input si leve	gnal I	Observa	tions
G	OVSAT	0	optrack	🗌 Pas	sed 🗌 Failed			Offset -45/low /Bw:4K	sig thr -80 (hz
S	SKY 5B	<sup>7</sup> 5B <b>0</b> optrack <sup>[]</sup> Pas		sed 🛛 Failed		Offset -45/low /Bw:4ł		sig thr -80 (hz	
S	SKY 5C 0 optrack $\Box$ Pas			sed 🛛 Failed		Offset -45/low sig /Bw:4Khz		sig thr -80 (hz	
S	SKY 5D 0 optrack $\Box$ Pa			🗌 Pas	sed 🗌 Failed			Offset -45/low /Bw:4K	sig thr -80 (hz
SC	SCRALL1B 0 optrack			Pas	sed Failed			Offset -45/low /Bw:4K	sig thr -80 (hz
SYR	SYRACUSE3A 0 optrack				sed 🗌 Failed			Offset -45/low /Bw:280	sig thr -80 Khz

		PROCEDURE / REPORT OF 1	rest № 1.5.1	
TEST NAMI Operatio	E: T2 Antenna nal checks	ELEMENT UNDER TEST: Antenna S	Subsystem	PROJECT: TSGT-DSO
		TABLE 1.5.1 'Satellite track da	ata table for T2"	
15.	Set OP_TRACK Step-track Mode Verify that the T Record Beacon Read the input s	Mode. Indicate the initialization conditions. e. erminal is pointing to the satellite in every case; signal level. ignal level from ACU.		☐ Passed ☐ Failed
16.	ACU Software P Deploy the anter command via M	re-limit set up and operation checks. Apply below checks nna, Record the AZ heading, calculate pre-limit, and ACS.		Passed  Failed
17.	Antenna AZ axis Command, Heac commanded val Command Heac • The An • Manual and rec • Manual	in clockwise (CW) direction and check: ding + 144 degree and check antenna moving to ue. ing + 145+1 degree and check tenna stops responding, "Command is out of range. ly (by PMU) move antenna to reach command value, read, ord the value when alarms appears. ly (by PMU) move antennas to reach CW limit Switch.	AZ <sub>CW</sub> = +145 <sup>o</sup> (Heading 205)+145+1=351 AZ CW SW fault AZ limit CW HW fault	AZ HEADING = AZ CW SW= AZ CW HW=
18.	Antenna AZ axis Command Heac commanded val Command Heac • The An • Manual and rec • Manual	in counter clockwise (CCW) direction and check: ing + (-144) degree and check antenna moving to ue. ing + (-145+1) degree and check tenna stops responding, "Command is out of range. ly (by PMU) move antenna to reach command value, read, ord the value when alarms appears. ly (by PMU) move antennas to reach CCW limit Switch.	AZ <sub>CCW</sub> = -145° (Heading 205)-145-1=59 AZ CCW SW fault AZ limit CCW HW fault	AZ <sub>HEADING</sub> = AZ CCW SW= AZ CW HW=

PROCEDURE / REPORT OF TEST № 1.5.1					
TEST NAME: T2 Antenna Operational checks		ELEMENT UNDER TEST: Antenna Subsystem		PROJECT: TSGT-DSO	
19.	Antenna EL DOV Command anten Command anten The An Manual and rec Manual	WN axis check: ana on the El-down axis to 6 <sup>o</sup> degrees ana on the El-down axis to 4 <sup>o</sup> degree and check tenna stops responding, "Command is out of range." ly (by PMU) move antenna to reach command value, read, ord the value when alarms appears. ly (by PMU) move antenna to reach down limit Switch.	EL <sub>DOWN</sub> = 5º EL DWN SW limit fault EL DWN HW limit fault	EL <sub>DOWN</sub> = SW=5 HW=	
20.	<ul> <li>Antenna EL UP axis check:</li> <li>Command antenna on the El-down axis to 79 ° degrees</li> <li>Command antenna on the El-down axis to 81 ° degree and check</li> <li>The Antenna stops responding, "Command is out of range.</li> <li>Manually (by PMU) move antenna to reach command value, read, and record the value when alarms appears.</li> <li>Manually (by PMU) move antennas to reach UP limit switch.</li> </ul>		EL UP =80° Command exceed EL UP+ EL UP SW limit fault EL UP HW limit fault	ELU <sub>P</sub> = SW= HW=	
21.	Apply Wind Up Test: 1. Place the antenna pointed at a stationary satellite. 2. Manually peak the signal. 3. Execute the Windup test. 4. Run the Windup test three times and verify that the results are similar for all runs. 5. Log Test result Typical Windup values should be less than 1% of the 3 dB beamwidth Beamwidth: $\frac{21}{freq x  dia}$ (Freq in GHz, Diameter in meters		<ul> <li>@ 7.405GHz:</li> <li>T2: 1.18°</li> <li>1% of BW</li> <li>T2: 0.0118°</li> </ul>	T2 Test #1: Az: 0.007 E1 : 0.005 T2 Test #2: Az: 0.007 E1 : 0.015 T2 Test #3: Az: 0.009 E1 : 0.004	

PROCEDURE / REPORT OF TEST Nº 1.5.1					
TEST NAME: T2 Antenna Operational checks		ELEMENT UNDER TEST: Antenna Subsystem		PROJECT: TSGT-DSO	
				□ Passed □ Failed	
22.	Check antenna Feed Membrane and Air leakage		Less than 2% on dehydrator	Passed      Failed	
23.	Check Elevation Steel Cables tension on the right-Hand side Not more than 1.00 +0.32" (2.6 cm) (factory setup)		(2.6 cm) (factory setup)	Cable #1 Cable #2 Cable #3 Cable #4 Cable #5 Cable #6	
24.	Check Elevation	Steel Cables tension and on the Left Hand side	(2.6 cm) (factory setup)	Cable #1 Cable #2 Cable #3 Cable #4 Cable #5 Cable #6	
25.	Check Azimuth	Steel Cables tension	(2.6 cm) (factory setup)	Cable #1 Cable #2 Cable #3 Cable #4	
26.	Check Azimuth	and El gear boxes.		Passed      Failed	
27.	Apply Elevation	Hand Crank operation		Passed      Failed	

PROCEDURE / REPORT OF TEST Nº 1.5.1						
TEST NAME: T2 Antenna Operational checks		ELEMENT UNDER TEST: Antenna S	ELEMENT UNDER TEST: Antenna Subsystem		PROJECT: TSGT-DSO	
28.	Apply Azimuth Hand Crank operation			□ Passed □ Failed		
29.	Apply Azimuth bearing operation			Passed      Failed		
30.	Check all cable harness, Feed boom struts, Feed pallet struts, Ferrous metal surfaces Painting, cracks and rusting Waveguide connections and support brackets			Passed  Failed		
31.	Apply recommended rust preventive re-coating on Ferrous parts and clean the dust and excessive oil			Passed      Failed		
32.	Apply De-icing system and blister check procedure			Passed D Failed		

#### 1.5.2 T1 ACU and ANTENNA DRIVE SYSTEM Test Procedure

PROCEDURE / REPORT OF TEST Nº 1.5.2						
TEST NAME: T1 Calibration		ELEMENT UNDER TEST: Antenna Subsystem		PROJECT: TSGT-DSO		
STEP	TEST SEQUENCE		EXPECTED RESULT	RESULT	REMARKS	
	Perform Note Tha	PMI I.A.W. procedure 600-1246C4 OPERATION & MAINTENANCE MANUAL FOR 46M TSGT at Limits are updated I.A.W. specific requirements				

PROCEDURE / REPORT OF TEST № 1.5.2							
TEST NAME: T1 Calibration		ELEMENT UNDER TEST: Antenna Subsystem		PROJECT: TSGT-DSO			
1.	Check T1 antenna for wear and tear, corrosion and painting removal available			Passed      Failed			
2.	Check Transport support X ties and ropes tying reflector			☐ Passed ☐ Failed			
3.	Check Trailer B	rakes and operation.		Passed      Failed			
4.	Check Air Suspension valve system and Air cushions operation.			Passed      Failed			
5.	Check Signal la	mps and Transport electrical devices on road operation.		Passed      Failed			
6.	Check that Trailer feet and supporters' pins are in place and working properly.			🗆 Passed 🔲 Failed			
7	Check Antenna and lubrication.	reflector EL Transport support bar and switch operation		🗆 Passed 🔲 Failed			
8	Check EL Motor	Transport support bar and switch operation.		Passed      Failed			
9	Check antenna feed locking pins and pads are in good condition.			🗆 Passed 🔲 Failed			
10	Check feed Assembly is in good condition after deploy the antenna			🗆 Passed 🔲 Failed			
11.	Check antenna feed is placing on stow brackets properly.			Passed      Failed			
12.	Check antenna maintained, safe mechanism wor Check in the ''lir when switch act	Stow Support Unit is in good condition pins and joints are and lubricated properly. Switch is functional and locking king properly. nit switch logic box <mark>'' STOW BRACKET '</mark> Led light is OFF uated		Passed  Failed			
PROCEDURE / REPORT OF TEST Nº 1.5.2							
--	--	--	-------------------	--------------------	--	--	--
TEST NAME: T1 Calibration         ELEMENT UNDER TEST: Antenna Su		ubsystem	PROJECT: TSGT-DSO				
13.	Check Antenna in good conditio	STOW Support Unit Velocity Switch, pads and spring are n and working properly.		Passed      Failed			
14.	Check Antenna Feed Waveguide Assembly connections are in good condition, tight and free of corrosion.			□ Passed □ Failed			
15.	Check antenna motors/brakes and lubrication and perform cleaning and lubrication for free operation I.A.W procedure, Lubrication and maintenance_T1_antenna			Passed  Failed			
16.	Check That, Power Drive Unit is mechanically rugged. Power on PDU			Passed      Failed			
17.	Power On ACU and configure for T1 operation. Capture print screen of ACU on ASNMC GUI.			Passed      Failed			
18.	Check ACU/PDI	J Link		Passed      Failed			
19.	Activate DEPLC compare read o	Y Mode antenna and check Compass heading and ut with handheld Compass		🗆 Passed 🔲 Failed			
20.	Make sure antenna is moving to deploy position and giving 'deployed'' Message		Deployed (@22.5)	Passed      Failed			
21.	Engage "HANDLE LATCH" Check in the 'limit switch logic box "HANDLE LATCH" Led light is OFF when switch actuated			Passed  Failed			
22.	DEPLOY Anten	na Wings		□ Passed □ Failed			

PROCEDURE / REPORT OF TEST Nº 1.5.2						
TEST NAME	: T1 Calibration	ELEMENT UNDER TEST: Antenna Su	ubsystem	PROJECT: TSGT-DSO		
	Check in the ''lim OFF when switcl Check in the ''lim OFF when switcl	hit switch logic box " <mark>L WING DEPLOYED'</mark> Led light is h actuated hit switch logic box " <mark>R WING DEPLOYED'</mark> Led light is h actuated				
23.	Check compass deploy	type and compass operation/activate Calibration after	TRUENORTH/ calibrate	Passed      Failed		
24.	Verify the absent Messages/Faults Read and Write screen Check that the "C Messages/Status moment, the GP Check GPS Qua Read and Write screen Check that the c	ce of the "ACU-GPS LINK DOWN" fault message in the s screen. down the coordinates as shown in Setup/Calibration GPS DATA UNAVAIL" message appears on the s screen. Wait until the message disappears. In this S receiver has acquired a valid site location. lity down the coordinates as shown in Setup/Calibration	Brunssum Best:9 Long.50.94E Lat.: 5.98N	☐ Passed ☐ Failed Long. Lat.:		
25.	Activate STOW I and record ante	Mode and check antenna stowing as required. And Check nna STOW command	Elevation Stow command -58	Command:		
26.	Check antenna is frame, Check AZ Check in the ''lim switch actuated	s center on AZ, properly to 0 degree and fitting into the Z STOW Centre switch operation. hit switch logic box <mark>" AZ CENT"</mark> Led light is OFF when	Check AZ center Offset =0 Check Centre Switch	Offset= 0.0 □ Passed □ Failed		

PROCEDURE / REPORT OF TEST Nº 1.5.2						
TEST NAME	TEST NAME: T1 Calibration         ELEMENT UNDER TEST: Antenna Subsystem			PROJECT: TSGT-DSO		
27.	STOW Antenna Wings Check in the ''limit switch logic box '' L WING STOWED' Led light is OFF when switch actuated Check in the ''limit switch logic box '' R WING STOWED'' Led light is OFF when switch actuated			Passed  Failed		
28.	Check antenna Stow Velocity switch speed Slowdown activation and stops Antenna Elevation Drive and unit creates STOWED message. Check in the "limit switch logic box <u>"EL VELOCITY"</u> Led light is OFF when switch actuated		Slow down velocity with activation of switch	☐ Passed ☐ Failed		
29.	Check Antenna STOWED messages and actual STOW position Check in the "limit switch logic box " STOWED" Led light is OFF when switch actuated		Elevation Stow actual value Stowed message	Actual Value:		
	Activate Emerge	ncy STOW mode with Wings open	HW Bypass ON	Passed      Failed		
30.	Apply Manual Az Check in the ''lin when switch actu	Z HAND CRANKING hit switch logic box <mark>" AZ HANDCRANK"</mark> Led light is OFF uated		Passed      Failed		
	Apply Manual EL Check in the ''lin when switch actu	- HAND CRANKING hit switch logic box <mark>" EL HANDCRANK"</mark> Led light is OFF uated		Passed      Failed		
31.	Check Manual A	CU/ Antenna JOG Commands		Passed      Failed		
32.	Check Satellite F	Preset list availability for 6 satellites		Passed Failed		

PROCEDURE / REPORT OF TEST № 1.5.2							
TEST NAME: T1 Calibration		ELEMENT UNDER TEST: Antenna S	ubsystem	PROJECT: TSGT-DSO	PROJECT: TSGT-DSO		
33.	Activate at least 2 different satellite searches and make sure antenna- tracking system is finding satellites. If cannot find satellites set proper Heading offset on the compass		Heading Offset:	Passed      Failed			
55.	calibration and record the value and records test results to "Satellite track data table for T1"						
	Set Op-track Mode. Indicate the initialization conditions.			Passed      Failed			
	Step-track Mode						
34.	Verify that the Te	erminal is pointing to the satellite in every case.					
	Record the signation	al level.					
	Read the input s	ignal level from ACU.					
			•	·			

SATELLITE NAME	Satellite Inclination	Track mode	S/S Antenna pointed	Input signal level	Observations
GOVSAT	0	optrack	☐ Passed ☐ Failed		Offset -45/low sig thr -80 /Bw:4Khz
SKY 5B	0	optrack	☐ Passed ☐ Failed		Offset -45/low sig thr -80 /Bw:4Khz
SKY 5C	0	optrack	Passed Erailed		Offset -45/low sig thr -80 /Bw:4Khz
SKY 5D	0	optrack	□ Passed □ Failed		Offset -45/low sig thr -80 /Bw:4Khz
SCRALL1B	0	optrack	□ Passed □ Failed		Offset -45/low sig thr -80 /Bw:4Khz
SYRACUSE3A	0	optrack	☐ Passed ☐ Failed		Offset -45/low sig thr -80 /Bw:280Khz

"Satellite track data table for T1"

PROCEDURE / REPORT OF TEST Nº 1.5.2							
TEST NAME: T1 Calibration         ELEMENT UNDER TEST: Antenna		ibsystem	PROJECT: TSGT-DSO				
		<u>.</u>		·			
35.	ACU Software F Deploy the anter command via M	re-limit set up and operation checks. Apply below checks nna, Record the AZ Heading, calculate pre-limit and ACS.		⊠ Passed □ Failed			
36.	Antenna AZ axis Command Head Command Head The An Manual and red Manually (by PM record the value movement Check in the "lin actuated	in clockwise (CW) direction and check: ing + 64 degree and check antenna moving to commanded ing + 65+1 degree and check tenna stops responding, "Command is out of range. ly (by PMU) move antenna to reach command value, read, ord the value when alarms appears. IU) move antennas to reach CW limit Switch. Read and when alarms appears. Check Hardware limit switch stops hit switch logic box "AZ CW" Led light is OFF when switch	AZ <sub>CW</sub> = (Heading 190)+64+1=258 AZ CW SW fault AZ limit CW HW fault	AZ HEADING = AZ CW SW= AZ CW HW=			
36	Antenna AZ axis Command Heac commanded val Command Heac • The An • Manua and rec Manually (by PM record the value movement	<ul> <li>in counter clockwise (CCW) direction and check:</li> <li>ing + (-64) degree and check antenna moving to ue.</li> <li>ing + (-65+1) degree and check</li> <li>tenna stops responding, "Command is out of range.</li> <li>ly (by PMU) move antenna to reach command value, read, cord the value when alarms appears.</li> <li>IU) move antennas to reach CCW limit Switch. Read and when alarms appears. Check Hardware limit switch stops</li> </ul>	AZ <sub>ccw</sub> = (Heading 190)+64+1=125 AZ CCW SW fault AZ limit CCW HW fault	AZ <sub>HEADING</sub> = AZ CCW SW= AZ CW HW=			

PROCEDURE / REPORT OF TEST Nº 1.5.2						
TEST NAME: T1 Calibration         ELEMENT UNDER TEST: Antenna Substance		ubsystem	n <b>PROJECT</b> : TSGT-DSO			
	Check in the ''lin switch actuated	it switch logic box <mark>" AZ CCW"</mark> Led light is OFF when				
37	<ul> <li>Antenna EL DOWN axis check:</li> <li>Command antenna on the El-down axis to 11 ° degrees</li> <li>Command antenna on the El-down axis to 9 ° degree and check         <ul> <li>The Antenna stops responding, "Command is out of range.</li> <li>Manually (by PMU) move antenna to reach command value, read, and record the value when alarms appears.</li> </ul> </li> <li>Manually (by PMU) move antenna to reach EL DOWN limit Switch. Read and record the value when alarms appears. Check Hardware limit switch stops movement</li> <li>Check in the "limit switch logic box " ELDOWN" Led light is OFF when switch actuated</li> </ul>		EL <sub>DOWN</sub> = 10 EL DWN SW limit fault EL DWN HW limit fault	ELdown = SW= HW=		
38	<ul> <li>38</li> <li>Antenna EL UP axis check:</li> <li>Command antenna on the El-down axis to 78 ° degrees</li> <li>Command antenna on the El-down axis to 80 ° degree and check <ul> <li>The Antenna stops responding, "Command is out of range.</li> <li>Manually (by PMU) move antenna to reach command value, read, and record the value when alarms appears.</li> </ul> </li> <li>38</li> <li>Manually (by PMU) move antenna to reach EL UP limit Switch. Read and record the value when an alarm appears. Check Hardware limits switches stops movement</li> <li>Check in the "limit switch logic box "EL UP" Led light is OFF when switch actuated</li> <li>Check in the "limit switch logic box "EL UP-BACKUP" Led light is OFF when switch actuated</li> </ul>		EL UP =80° Command exceed EL UP+ EL UP SW limit fault EL UP HW limit fault	ELUP= SW= HW= FINALHW:		

PROCEDURE / REPORT OF TEST № 1.5.2							
TEST NAME: T1 Calibration         ELEMENT UNDER TEST: Antenna S			ubsystem PROJECT: TSGT-DSO				
39	<ul> <li>Lubrica Noise</li> </ul>	te EL Drive Shaft and check motor operations without any		Passed      Failed			
40	Lubricate AZ Drive Sector and check motor operations without any Noise			🗆 Passed 🔲 Failed			
41	<ul> <li>Open, clean and Check AZ Brake and clutch system functioning properly</li> </ul>			🗌 Passed 🔲 Failed			
42.	Apply Wind Up Test: 1. Place the antenna pointed at a stationary satellite. 2. Manually peak the signal. 3. Execute the Windup test. 4. Run the Windup test three times and verify that the results are similar for all runs. 5. Log Test result Typical Windup values should be less than 1% of the 3 dB beamwidth Beamwidth: $\frac{21}{freq x dia}$ (Freq in GHz, Diameter in meters		@ 7.405GHz: T1: 0.62° 1% of BW T1: 0.0062°	T1 Test #1:         Az: 0.007         E1 : 0.005         T1 Test #2:         Az: 0.007         E1 : 0.015         T1 Test #3:         Az: 0.009         E1 : 0.004         □ Passed □ Failed			
43.	Check antenna I	Feed Membrane and Air leakage		□ Passed □ Failed			
44.	Apply De-icing s Only one SSPA antenna Anti-Icir Only one ECU c	ystem and blister check procedure (T-2) and one TWTA Beam (T-1) can be turn ON when ng is enable. an be in operation when Antenna Anti-Icing is enable.		☐ Passed ☐ Failed			

#### **1.5.3 T1 ANTENNA EMERGENCY STOP VERIFICATION**

PROCEDURE / REPORT OF TEST № 1.5.3								
TEST NAME: Emergency         ELEMENT UNDER TEST: Antenna Sub           Stop verification         ELEMENT UNDER TEST: Antenna Sub		ubsystem	PROJECT: TSGT-DSO					
STEP		TEST SEQUENCE	EXPECTED RESULT	RESULT	REMARKS			
1.	Push the Antenr Verify that the a	na Emergency Power Stop button. ntenna trailer is unpowered.		🗆 Passed 🔲 Failed				
2.	Power-on the TS Move the anteni Push the ACU E not move.	SGT and wait for the equipment to start-up. ha by means of the ACU front panel or MACS. Emergency Stop button and Verify that the Antenna does		Passed  Failed				
3.	Check the Alarn	ns in MACS		Passed      Failed				
4.	Check functiona	lity of "Safe to Rotate" button on T1		Passed      Failed				

#### 1.6 ASNMC FUNTIONALTY TEST

PROCEDURE / REPORT OF TEST № 1.6.1								
TEST NAME: ASNMC		ELEMENT UNDER TEST: ASNMC		PROJECT: TSGT-DSO				
STEP		TEST SEQUENCE		RESULT	REMARKS			
1.	ASNMC_Functionalty_Test_Procedure Open Computer and check Fan operations clean inlet and outlets			☐ Passed ☐ Failed				
2.	Check available Ba	ackup batteries and replace if needed		Passed      Failed				

	PROCEDURE / REPORT OF TEST № 1.6.1							
TEST NAME: ASNMC ELEMENT UNDER TEST: ASNI		NMC	PROJECT: TSGT-DSO					
3.	Check ASNMC Co properly	mputer is having latest version installed and functioning	Win7 prof. ASNMC Ver.1.2.2 Beta	Passed      Failed				
4.	Check ASNMC Co installed and funct	omputer is having latest desktop NCIA BG Info logo ioning properly		☐ Passed ☐ Failed				
5.	Check the IP confi IP address.	guration recording to be sure the MACS has the proper		☐ Passed ☐ Failed				
6.	Check RDP (Remote Desk Top operation) Functioning properly			Passed      Failed				
7.	Check SMS kit Installation perform and if Ports are configured.			Passed      Failed				
8.	Check iDirect EOW modem is reachable via ASNMC Computer. Download modem configuration to desktop and check modem is having latest operational option file loaded. (desired for dedicated Network)			Passed  Failed				
9.	Configure EOW iD follow; CW, CF 95	irect modem of the ASNMC or signal generator as 0 MHz, Output power -15 dBm.		Passed      Failed				
10.	Configure setup fo the T1 Antenna. CF 950 MHz CF 1200 MHz CF 1450 MHz	r T1, measure the CW signal at the TX Power out port of	LBAND /XBAND -23.5dBm /33.0 dBm -23.5dBm /33.0 dBm -23.5dBm /33.0 dBm	Passed  Failed				
11.	Configure setup fo /Read, and record CF 950 MHz CF 1200 MHz	r T2, measure on "RF TX OUT", apply measurements for the value measured.	LBAND /XBAND -23.4dBm /38.0 dBm -23.4dBm /38.0 dBm -23.4dBm /38.0 dBm	Passed  Failed				

PROCEDURE / REPORT OF TEST № 1.6.1						
TEST NAME:	ASNMC	ELEMENT UNDER TEST: A	SNMC	PROJECT: TSGT-DSO		
	CF 1450 MHz					
12.	Go to the right sate the IDirect modem Switch the HPA's o are steady green	ellite (depending on the option file) and make sure that gets Rx lock. The most left LED will be steady green. combined to antenna and wait till all LED's on the modem	Sync/ All LED's green	Passed      Failed		
	Capture print scree	en of iDirect on ASNMC GUI.				
		# Idirect [Connected]				
		Gene	eral alarm Normal			
		Tx rate (Kbps) 1015.313 Tx type Tx modulation Tx FEC	Burst     Tx state     Enabled       QPSK     RF ON     RF OFF       TPC0.793			
		Rx rate (Kbps) 1015.313 Rx type Rx freq. (MHz) Rx modulation Rx FEC	SCPC         Rx state         Enabled           956.699         SNR (dB)         11.2           QPSK         Rx AGC (dBm)         -22.66           TPC0.793			
		Common       Status     Normai       Access       Network     Enabled       Temperature (°C)     26	Normal Reset			
13.	Logon to the LCA a	and start the ASNMC software.		Passed      Failed		
	Double click on the resulting window, N	NCCx_Access field and make sure that, in the NCCA and NCCP access is available over ICC.				
	Capture print scree	n of NCCx Access on ASNMC GUI.				

			F	ROCEDURE / REPOR	RT OF TEST Nº 1.6.1			
TEST NAME:	ASNMC		ELEN	IENT UNDER TEST: A	SNMC	PROJECT: T	PROJECT: TSGT-DSO	
		·						
		<b>#</b> N	CCx Access [Connect	ted]				
		L.	CCP access NCCP def. active route NCCP via ICC NCCP ICC hub	General alarm ASNMC router interfac NR LAN NGCS VRF ICC VRF EMS VRF ICC ICC Available F11	Normal es Available Available Available Available Available NCCA access NCCA def. active route IC NCCA via ICC Avai NCCA ICC Avai NCCA ICC F1	C able		
			NCCP via NGCS NCCP via EMS	Unavailable Unavailable	NCCA via NGCS Unava NCCA via EMS Unava	ilable ilable		
14.	Connect the SNOM channel on the exte	I NR IP phone ended iDirect	to the dedicated po modem port perform	ort on the EOW n a functionality test		Passec	d 🗌 Failed	
15.	Establish connectiv post connect SNOI SW and perform a	vity between th M NU IP phone functionality te	e ASNMC VPN rou to the dedicated p est	ter and the remote ort on the remote port		Passec	d 🗌 Failed	
	On the SNOM 305 Advanced menu: - Select Qo - On the se Registar.	phones, use the phones, use the phones, use the phone th	ne Web-interface a locate the: <i>Filter F</i> alue to <u>OFF</u>	nd select the Packets From	QoS/Security >Filter Packets From Registar > set the value to <u>OFF</u>		5 🗌 Failed	

	PROCEDURE / REPORT OF TEST № 1.6.1								
TEST NAME:	ASNMC	ELEMENT UNDER TEST: AS	PROJECT: TSGT-DSO						
16.	Establish connectivity between the ASNMC VPN router and connect the remote ASNMC computer to the dedicated port on the Remote port SW and perform a functionality test			Passed      Failed					
17.	Establish connectiv M&C computer and	vity between the ORION M&C switch and the remote d perform a functionality test		Passed      Failed					
18.	Log on to ASNMC DWS computer and check current ASNMC GUI version for Ver. ASNMC Ver.1.2.1		Win7 prof. ASNMC Ver.1.2.2 Beta	Passed      Failed					
19.	Check ASNMC DV installed and functi	VS Computer is having latest desktop NCIA BG.Info logo toning properly		Passed      Failed					
20.	Log on VPN ROUT Fans and Backup I	FER/SWITCH and Check Configured Properly. Cooling battery is keeping configuration.		Passed D Failed					

#### EMS TEST

#### 1.7 EMS CW CARRIER TRANSMISSION

	Test Procedure / REPORT OF TEST № 1.7.1								
TEST NAME: transmission.	TEST NAME: T-1 only EMS CW carrier       ELEMENT UNDER TEST: Effective         transmission.       ELEMENT UNDER TEST: Effective			PROJECT: TSGT-DSO					
STEP		TEST SEQUENCE	EXPECTED RESULT	RESULT	REMARKS				
1.	1.7.1_20150127_NU_EMS_Fun Open Computer and check Fan	ctionalty_Test_Procedure operations clean inlet and outlets		☐ Passed ☐ Failed					
2.	Check available Backup batterie	s and replace if needed		Passed  Failed					
3.	Check EMS Computer and VM is communicating	s having latest Firmware/SW installed and	V.02.01.12	Passed  Failed					
4.	Check EMS 8U Modem Rack is communicating Logging-on to LMC, launch L	having latest Firmware/SW installed and MS. > <i>Display MR auto test</i> .		Passed  Failed					
5.	Check EMU card is working Pro	perly	Only 8U Modem Rack	🛛 Passed 🛛 Failed					
6.	Check EMU Card Version is con	rect and upgraded to the latest.		Passed 🗌 Failed					

			Test Procedu	IRE / REPORT OF T	EST № 1.7.1		
TEST NAME: transmission.	T-1 only EMS CW carrie	r	ELEME	NT UNDER TEST: E	MS	PROJECT: TSGT-DSO	
	Component	Versie	on Sub-component	Version			
			LIA	V3.01			
			BOOTPP	V4.09			
	EMU	V9.6	TESTCAGE	V5.28			
			GESTCARMIN	V1.15			
			LCTL-EMU	V9.6			
	-	•					
7.	Check ECU card is wo	rking Prop	erly	Only 8U Modem Rack	🛛 Passed 🗌 Failed		
	Check ECU Card Vers	ion is corre	ect and upgraded to the latest.			⊠ Passed □ Failed	
8.	FOU		SMS	V1.1			
	ECU	V1.1	STS	V1.1			
	' 		I				
9.	Check CU card #1 is working Properly				Only 8U Modem Rack	☐ Passed ☐ Failed	
10.	Check CU Card #1 Ve	rsion is cor	rrect and upgraded to the latest.			⊠ Passed □ Failed	

			Test Procedu	re / REPORT OF TE	ST Nº 1.7.1		
TEST NAME: transmission.	T-1 only EMS CW carrie	ſ	ELEME	NT UNDER TEST: E	MS	PROJECT: TSGT-DSO	
	UC G2.0	Ed2 V3.04	FPGATEST FPGAMFC2 <sup>1</sup> BOOTPP DSP_LPP DSP_NEMS <sup>2</sup> DSP_TEST LOG_OPE LIA	01.01 02.10 05.03 03.03 03.23 03.02 12K20 04.04			
11.	Check CU card #2 is working Properly			Only 8U Modem Rack	□ Passed □ Failed		
	Check CU Card #2 Version is correct and upgraded to the latest.					🛛 Passed 🗌 Failed	
12.	UC G2.0	Ed2 V3.04	FPGATEST FPGAMFC2 <sup>1</sup> BOOTPP DSP_LPP DSP_NEMS <sup>2</sup> DSP_TEST LOG_OPE LIA	01.01 02.10 05.03 03.03 03.23 03.02 12K20 04.04			
13.	Check CU card #3 is w	orking Prop	erly		Only 8U Modem Rack	Passed      Failed	
14.	Check CU Card #3 Ver	rsion is corre	ect and upgraded to the latest.			Passed 🗌 Failed	

	Test Procedure / REPORT OF TEST № 1.7.1								
TEST NAME: transmission.	T-1 only EMS CW carrie	r	ELEMEI	NT UNDER TEST: E	MS	PROJECT: TSGT-DSO			
	UC G2.0	Ed2 V3.04	FPGATEST FPGAMFC2 <sup>1</sup> BOOTPP DSP_LPP DSP_NEMS <sup>2</sup> DSP_TEST LOG_OPE LIA	01.01 02.10 05.03 03.03 03.23 03.02 12K20 04.04					
15.	Check CU card #4 is working Properly			Only 8U Modem Rack	Passed      Failed				
	Check CU Card #4 Version is correct and upgraded to the latest.					🛛 Passed 🗌 Failed			
16.	UC G2.0	Ed2 V3.04	FPGATEST FPGAMFC2 <sup>1</sup> BOOTPP DSP_LPP DSP_NEMS <sup>2</sup> DSP_TEST LOG_OPE LIA	01.01 02.10 05.03 03.03 03.23 03.02 12K20 04.04					
17.	Check CU card #5 is w	orking Prope	erly		Only 8U Modem Rack	Passed      Failed			

	Test Procedure / REPORT OF TEST № 1.7.1								
TEST NAME: transmission.	T-1 only EMS CW car	rrier	ELEN	IENT UNDER TEST: E	MS	AS PROJECT: TSGT-DSO			
	Check CU Card #5	Version is correct	and upgraded to the lates		🛛 Passed 🗖 Failed				
			FPGATEST	01.01					
			FPGAMFC21	02.10					
			BOOTPP	05.03					
18		Ed2	DSP_LPP	03.03					
	UC G2.0	V3.04	DSP_NEMS <sup>2</sup>	03.23					
			DSP_TEST	03.02					
			LOG_OPE	12K20					
			LIA	04.04					
19.	Move one of the CU	cards to slot #6 a	nd Check CU card slot #6	) is working Properly	Only 8U Modem Rack				
20.	Check PSU #1 is wo	orking Properly			Only 8U Modem Rack	Passed      Failed			
21.	Check PSU #2 is wo	orking Properly			Only 8U Modem Rack	□ Passed □ Failed			
22.	Check PSU #3 is wo	orking Properly			Only 8U Modem Rack	□ Passed □ Failed			
23.	Check PSU #4 is wo	orking Properly			Only 8U Modem Rack	Passed Failed			
24.	Check cooling fan T	ry fans are running	g Properly		Only 8U Modem Rack	□ Passed □ Failed			
25.	Replace ECU card board.	back-up battery an	nd Stick a battery replacen	nent date label on the	Only 8U Modem Rack	□ Passed □ Failed			

	Test Procedure / REPORT OF TEST № 1.7.1								
TEST NAME: transmission.	T-1 only EMS CW carrier	ELEMENT UNDER TEST	: EN	MS PROJECT: TSGT-DSO					
26.	Apply 10 MHz reference calibrati	on on 8U Modem Rack		Only 8U Modem Rack	□ Passed □ Failed				
	EMS 8U M	SET THE FREQUENCY COUNTER • Connect the frequency counter to	he .	J1 connector (SMB conn Adjusting potentiomet 10 MHz ref Frequency of	iector). ter ference				
27.	Select Up-converter A ONLINE a Configure modem EPM, CU#1 a -15dBm. Connect the power meter sensor measure the level. Make a LBAND BNC loop from U Record the RX Power Level on th Connect the power sensor to X E the level. (Coupler 57dbc) Record the measured value for C Record the measured value for C	and SSPA A + B ONLINE. s follow; CW, CF 1200 MHz, Output power to LBAND P/P EMS 1 and Enable CW and JPLINK to/DOWNLINK Patch Panel. he LMS as seen below. BAND RF test Panel and Enable CW and measure CF 950 MHz -15dBm. CF 1450 MHz -15dBm.		LBANDTX:-16.8dbm BAND RX:-17.5dbm X -BAND TX T1:+40.0dBM X- BAND TX T2:+46.0dBM	☐ Passed				

		Test Procedure / REPORT OF T	EST № 1.7.1		
TEST NAME: transmission.	T-1 only EMS CW carrier	ELEMENT UNDER TEST: E	PROJECT: TSGT-DSO	PROJECT: TSGT-DSO	
	Install TX, RX RF Chain for CUs.				
28.	Select Up-converter A ONLINE a Configure modem EPM, CU#2 a -15dBm. Connect the power meter sensor measure the level. Make a LBAND BNC loop from L Record the RX Power Level on th Connect the power sensor to X E the level. (Coupler 57dbc) Record the measured value for C Record the measured value for C	and SSPA A + B ONLINE. s follow; CW, CF 1200 MHz, Output power to LBAND P/P EMS 2 and Enable CW and JPLINK to/DOWNLINK Patch Panel. he LMS as seen below. BAND RF test Panel and Enable CW and measure CF 950 MHz -15dBm. CF 1450 MHz -15dBm.	LBANDTX: -16.8dbm LBAND RX: -17.5dbm X -BAND TX T1: +40.0dBM X- BAND TX T2: +46.0dBM	Passed  Failed	
29.	Select Up-converter A ONLINE a Configure modem EPM, CU#3 a -15dBm. Connect the power meter sensor measure the level. Make a LBAND BNC loop from L Record the RX Power Level on th Connect the power sensor to X E	and SSPA A + B ONLINE. s follow; CW, CF 1200 MHz, Output power to LBAND P/P EMS 3 and Enable CW and JPLINK to/DOWNLINK Patch Panel. he LMS as seen below. BAND RF test Panel and Enable CW and measure	LBANDTX: -16.8dbm LBAND RX: -17.5dbm X -BAND TX T1: +40.0dBM X- BAND TX T2: +46.0dBM	☐ Passed ☐ Failed	

		Test Procedure / REPORT OF T	EST № 1.7.1		
TEST NAME: transmission.	T-1 only EMS CW carrier	ELEMENT UNDER TEST: E	PROJECT: TSGT-DSO	PROJECT: TSGT-DSO	
	Record the measured value for 0 Record the measured value for 0	CF 950 MHz -15dBm. CF 1450 MHz -15dBm.			
30.	Select Up-converter A ONLINE a Configure modem EPM, CU#4 a -15dBm. Connect the power meter sensor measure the level. Make a LBAND BNC loop from U Record the RX Power Level on t Connect the power sensor to X E the level. (Coupler 57dbc) Record the measured value for C Record the measured value for C	and SSPA A + B ONLINE. s follow; CW, CF 1200 MHz, Output power r to LBAND P/P EMS 4 and Enable CW and JPLINK to/DOWNLINK Patch Panel. he LMS as seen below. BAND RF test Panel and Enable CW and measure CF 950 MHz -15dBm. CF 1450 MHz -15dBm.	LBANDTX: -16.8dbm LBAND RX: -17.5dbm X -BAND TX T1: +40.0dBM X- BAND TX T2: +46.0dBM	☐ Passed	
31.	Select Up-converter A ONLINE a NOTE THAT THIS CU CARD IS PANELS Configure modem EPM, CU#5 a -15dBm. Connect the power meter sensor measure the level. Make a LBAND BNC loop from U Record the RX Power Level on t Connect the power sensor to X E the level. (Coupler 57dbc)	and SSPA A + B ONLINE. NOT WIRED TO IFL UP/DOWN LINK PTACH s follow; CW, CF 1200 MHz, Output power r to LBAND P/P EMS 5 and Enable CW and JPLINK to/DOWNLINK Patch Panel. he LMS as seen below. BAND RF test Panel and Enable CW and measure	LBANDTX: -16.8dbm LBAND RX: -17.5dbm X -BAND TX T1: +40.0dBM X- BAND TX T2: +46.0dBM	☐ Passed ☐ Failed	

	Test Procedure / REPORT OF TEST № 1.7.1							
TEST NAME: transmission.	T-1 only EMS CW carrier	ELEMENT UNDER TEST: E	PROJECT: TSGT-DSO					
	Record the measured value for 0	CF 950 MHz -15dBm.						
	Record the measured value for 0	CF 1450 MHz -15dBm.						
	Select Up-converter A ONLINE a	and SSPA A + B ONLINE.	LBANDTX: -16.8dbm					
	MOVE CU#5 to CU SLOT# 6							
	NOTE THAT THIS CU CARD IS PANELS	NOT WIRED TO IFL UP/DOWN LINK PTACH	LBAND RX: -17.5dbm	Passed      Failed				
	Configure modem EPM, CU#5 a -15dBm.	s follow; CW, CF 1200 MHz, Output power	X -BAND TX T1: +40.0dBM					
32.	Connect the power meter sensor measure the level.	r to LBAND P/P EMS 5 and Enable CW and	X- BAND TX T2: +46 0dBM					
	Make a LBAND BNC loop from l	JPLINK to/DOWNLINK Patch Panel.	++0.00DM					
	Record the RX Power Level on t	he LMS as seen below.						
	Connect the power sensor to X E the level. (Coupler 57dbc)	BAND RF test Panel and Enable CW and measure						
	Record the measured value for 0	CF 950 MHz -15dBm.						
	Record the measured value for 0	CF 1450 MHz -15dBm.						
	Establish a test configuration	and apply online test.		☐ Passed ☐ Failed				
1.	Check EMSe 1U Modems 1 is ha	aving latest Firmware/SWS installed and	ETX upgrade to V4.3.23 Versión V1.2.3 with	Passed I Failed				

				Test Procedu	IFE / REPORT OF TI	EST № 1.7.1		
TEST NAME: transmission.	T-1 only EMS CW carrie	r	ELEMENT UNDER TEST: EMS			PROJECT: TSGT-DSO	PROJECT: TSGT-DSO	
	Component	Versi	ion	Sub-component	Version			
				FIP	V5.03			
	ETX	i3.4.23		SOCIP21E	V4.3.23			
				Factory File	V6.3.NE.5			
				LIA	04.04			
				BOOTPP	05.03			
			DSP_TEST	04.11				
				DSP_LPP	04.13			
				FPGATEST	02.17			
	UC G2.1	Ed2		CALIB_UC <sup>1</sup>	03.03			
		V4.03		DSP_NEMS <sup>2</sup>	04.03			
				FPGAMFC2 <sup>3</sup>	02.10			
		Ed3		F_4606E34	60.05			
		V3.32		D_4606E35	03.50			
				LOG_OPE	12K20			
2.	2. Check EMSe 1U Modems 2 is having latest Firmware/SWS installed and communicating				ETX upgrade to V4.3.23 Versión V1.2.3 with CU V.04.03ETX upgrade to V4.3.23	Passed  Failed		

	Test Procedure / REPORT OF TEST № 1.7.1							
TEST NAME: transmission.	T-1 only EMS CW carrie	ſ	ELEME	NT UNDER TEST: E	EMS	PROJECT: TSGT-DSO		
	Component Vers		n Sub-component	Version				
			FIP	V5.03				
	ETX	i3.4.23	SOCIP21E	V4.3.23				
			Factory File	V6.3.NE.5				
			LIA	04.04				
			BOOTPP	05.03				
			DSP_TEST	04.11				
			DSP_LPP	04.13				
			FPGATEST	02.17				
	UC G2.1	Ed2	CALIB_UC <sup>1</sup>	03.03				
		V4.03	DSP_NEMS <sup>2</sup>	04.03				
			FPGAMFC2 <sup>3</sup>	02.10				
		Ed3	F_4606E3 <sup>4</sup>	60.05				
		V3.32	D_4606E35	03.50				
			LOG_OPE	12K20				
3.	Check EMSe 1U Mode communicating	ms 3 is hav	ing latest Firmware/SWS install	ed and	ETX upgrade to V4.3.23 Versión V1.2.3 with CU V.04.03Versión V1.2.3 with CU V.04.03	☐ Passed ☐ Failed		

	Test Procedure / REPORT OF TEST № 1.7.1							
TEST NAME: transmission.	T-1 only EMS CW carrie	r		ELEME	NT UNDER TEST: E	MS	PROJECT: TSGT-DSO	
	Component Vers		ion	Sub-component	Version			
				FIP	V5.03			
	ETX i3.4.20	3	SOCIP21E	V4.3.23				
				Factory File	V6.3.NE.5			
				LIA	04.04			
			BOOTPP	05.03				
			DSP_TEST	04.11				
			_	DSP_LPP	04.13			
				FPGATEST	02.17			
	UC G2.1	Ed2		CALIB_UC <sup>1</sup>	03.03			
		V4.03	;	DSP_NEMS <sup>2</sup>	04.03			
				FPGAMFC2 <sup>3</sup>	02.10			
		Ed3		F_4606E34	60.05			
		V3.32	2	D_4606E35	03.50			
				LOG_OPE	12K20			
4.	Check EMSe 1U Moder communicating	ms 4 is ha	aving late	est Firmware/SWS instal	led and	ETX upgrade to V4.3.23 Versión V1.2.3 with CU V.04.03ETX upgrade to V4.3.23	Passed  Failed	

	Test Procedure / REPORT OF TEST № 1.7.1						
TEST NAME: transmission.	T-1 only EMS CW carrie	er	ELEMEI	NT UNDER TEST:	EMS	PROJECT: TSGT-DSO	
	Component	Version	on Sub-component Version				
			FIP	V5.03			
	ETX	i3.4.23	SOCIP21E	V4.3.23			
			Factory File	V6.3.NE.5			
			LIA	04.04			
			BOOTPP	05.03			
			DSP_TEST	04.11			
			DSP_LPP	04.13			
			FPGATEST	02.17			
	UC G2.1	Ed2	CALIB_UC <sup>1</sup>	03.03			
		V4.03	DSP_NEMS <sup>2</sup>	04.03			
			FPGAMFC2 <sup>3</sup>	02.10			
		Ed3	F_4606E34	60.05			
		V3.32	D_4606E35	03.50			
			LOG_OPE	12K20			
	Establish a test conf	iguration and	d apply online test.			Passed      Failed	
		modie hereit	ng lataat Firmwara (0)//0 is stall	ad and	Versión V1.2.1 with		
1.	communicating.	ems i is navir	ng latest Firmware/SWS install	ed and	ETX upgrade to		
					V4.3.23		
2.	Check EMSe 1U Mode	ems 2 is havir	ng latest Firmware/SWS install	ed and	FTX upgrade to		
	communicating				V4.3.23		
	Chook EMSo 111 Mod	ma 2 ia havin	ng lataat Eirmwara/SM/S isatall	ad and	Version V1.2.1 with		
3.	communicating	ems 3 is navir	ng latest Firmware/SWS Install	eu and	ETX upgrade to		
	Ŭ				V4.3.23		

		Test Procedure / REPORT OF 1	EST № 1.7.1		
TEST NAME: transmission.	T-1 only EMS CW carrier	ELEMENT UNDER TEST:	PROJECT: TSGT-DSO		
4.	Check EMSe 1U Modems 4 is ha	Version V1.2.1 with ETX upgrade to V4.3.23			
5.	<ul> <li>Apply 10 MHz reference calibration</li> <li>Connect Frequency Construction</li> <li>Disconnect 10 MHz support</li> <li>Internal Frequency show</li> <li>If not, remove the + screet</li> </ul>	ion on EMSe1U Modem#1 unter to the BNC port at the front panel of the EMSe. oplied from NETCLOCK at the back of the EMSe. uld be 10 MHz, +/-10Hz on the Frequency Counter. ew at the front of the EMSe and adjust it for 10 MHz	10.000.000Hz. Level: +1.04dbm		
6.	Apply 10 MHz reference calibrati	ion on 1U Modem#2	10.000.000Hz. Level: +0.99dbm	Passed  Failed	
7.	Apply 10 MHz reference calibrati	ion on 1U Modem#3	10.000.000Hz. Level: +0.89dbm	Passed  Failed	
8.	Apply 10 MHz reference calibrati	ion on 1U Modem#4	10.000.000Hz. Level: +0.89dbm	Passed D Failed	
	Select Up-converter A ONLINE a Configure modem EPM, TU1, (E power -15dBm.	and SSPA A + B ONLINE. MSe #1) as follow; CW, CF 1200 MHz, Output			
9.	Connect the power meter sensor measure the level. Make a LBAND BNC loop from U	r to LBAND P/P EMSe1 and Enable CW and JPLINK to/DOWNLINK Patch Panel.	LBAND RX: -17.41dbm	Passed      Failed	EMSe1
	Record the RX Power Level on t	he LMS as seen below.			

	Test Procedure / REPORT OF TEST № 1.7.1						
TEST NAME: T-1 only EMS CW carrier transmission.		ELEMENT UNDER TEST: EMS		PROJECT: TSGT-DSO			
	Connect the power sensor to X E the level. (Coupler 57dbc)	BAND RF test Panel and Enable CW and measure	XBAND TX T2: +44.00dBM				
	Record the measured value for 0	CF 950 MHz -15dBm.					
	Record the measured value for 0	CF 1450 MHz -15dBm.					
	Install TX,RX RF Chain for CUs.						



Test Procedure / REPORT OF TEST № 1.7.1						
<b>TEST NAME:</b> T-1 only EMS CW carrier transmission.		ELEMENT UNDER TEST: E	PROJECT: TSGT-DSO	PROJECT: TSGT-DSO		
10.	Select Up-converter A ONLINE a Configure modem EPM, TU2, (E power -15dBm. Connect the power meter sensor measure the level. Make a LBAND BNC loop from L Record the RX Power Level on th Connect the power sensor to X E the level. (Coupler 57dbc) Record the measured value for C Record the measured value for C Install TX,RX RF Chain for CUs.	and SSPA A + B ONLINE. MSe #2) as follow; CW, CF 1200 MHz, Output T to LBAND P/P EMSe2 and Enable CW and JPLINK to/DOWNLINK Patch Panel. he LMS as seen below. BAND RF test Panel and Enable CW and measure CF 950 MHz -15dBm. CF 1450 MHz -15dBm.	LBANDTX: -17.50dbm LBAND RX: -23.2dbm X- BAND TX T2: +44.1dBM	☐ Passed	EMSe2	

Test Procedure / REPORT OF TEST № 1.7.1						
TEST NAME: T-1 only EMS CW carrier transmission.	ELEMENT UNDER TEST: EMS	PROJECT: TSGT-DSO				
LMS - Monitoring and control [OLUX]         View       Ierminal Control and Monitoring 1         View       Ierminal Control and Monitoring 1         Available resources       OLUX         Image: P. Modems       Image: TU 1         Image: P. Modems       Image: TX RF Chains         Image: P. Modems       Image: TX RF Chains	ganagement Eallback Permission Protected Moderns Window         Image: Constrained State Stat	Image: Status       Tx       Rx       Termining         ary Modem       Backup Modem       Status       Tx       Rx       Termining				
Entry Configuer Detta Z Termina do Links Ready	Terminal j Links list 🖉 Links 📾 P. Modems 🖤 MR	EMCON CNX AdminLMC				

Test Procedure / REPORT OF TEST № 1.7.1						
TEST NAME: T-1 only EMS CW carrier transmission.		ELEMENT UNDER TEST: E	PROJECT: TSGT-DSO	PROJECT: TSGT-DSO		
11.	Select Up-converter A ONLINE a Configure modem EPM, TU3, (E power -15dBm. Connect the power meter sensor measure the level. Make a LBAND BNC loop from L Record the RX Power Level on th Connect the power sensor to X E the level. (Coupler 57dbc)	and SSPA A + B ONLINE. MSe #3) as follow; CW, CF 1200 MHz, Output to LBAND P/P EMSe1 and Enable CW and JPLINK to/DOWNLINK Patch Panel. he LMS as seen below. BAND RF test Panel and Enable CW and measure	LBANDTX: -17.40dbm LBAND RX: -22.2dbm	☐ Passed ☐ Failed	EMSe3	
	Record the measured value for C Record the measured value for C Install TX,RX RF Chain for CUs.	CF 950 MHz -15dBm. CF 1450 MHz -15dBm.	+44.2dBM			



Test Procedure / REPORT OF TEST № 1.7.1							
TEST NAME: transmission.	T-1 only EMS CW carrier	ELEMENT UNDER TEST: E	PROJECT: TSGT-DSO				
12.	Select Up-converter A ONLINE a Configure modem EPM, TU4, (E power -15dBm. Connect the power meter sensor measure the level. Make a LBAND BNC loop from L Record the RX Power Level on th Connect the power sensor to X E the level. (Coupler 57dbc) Record the measured value for C Record the measured value for C Install TX, RX RF Chain for CUs	and SSPA A + B ONLINE. MSe #4) as follow; CW, CF 1200 MHz, Output to LBAND P/P EMSe4 and Enable CW and JPLINK to/DOWNLINK Patch Panel. he LMS as seen below. BAND RF test Panel and Enable CW and measure CF 950 MHz -15dBm. CF 1450 MHz -15dBm.	LBANDTX: -16.8dbm LBAND RX: -17.5dbm X- BAND TX T2: +44.0dBM	☐ Passed ☐ Failed	EMSe4		

#### 1.8 BER STABILITY TEST PER ITU- G.821 STANDARD

	PROCEDURE / REPORT OF TEST Nº 1.8.1								
TEST NAME: BER stability Test ELEMENT UNDER TEST: Satellite			System	PROJECT: TSGT-DSO					
STEP		TEST SEQUENCE	EXPECTED RESULT	RESULT	REMARKS				
1.	Obtain satellite A Terminals and / Configure system requirements Select BUC A an Select LNA A an Point the Antenn	Access Authorization to link TSGT with other NATO or a NATO Hub Station over a Multilink. m for T1or T2 configuration depends on the power nd SSPA A + B. nd BDC A. na Subsystem at the Satellite.							
2.	<ul> <li>Configure the EBEM1</li> <li>I.A.W the SAA's. (SAT Loop) See Configuration below.</li> <li>Verify that TSGT, EBEM1 is lock.</li> </ul>								
3	Configure BER is free of any error	TESTER in the MODEM, start the BER test and verify test rors. Inject 1 Error and see it.							

PROCEDURE / REPORT OF TEST № 1.8.1											
TEST NAME: BER stab Test	ER stability ELEMENT UNDER TEST: Sa			ER TEST: Satell	te System		PR	ROJECT: TSGT-DS	0		
Ebem 1 [Connected]     Modem status     Reset     Zeroize     Carrier lock     Eth. bit sync.     Reboot     General     ESEM ITA_AUPC     Tests     Freq. (MHz)     I211     Serial DR (kbps)     20	US Ready TX Normal Eb, No Sync Es, status Synchroni Rx Remote RX ort Export ts Alarms 12.569 R Freq. 348.0 Seria	: status         On           i.evel (dBm)         -18.00           j/No (dB)         10.47           j/No (dB)         14.66           (vevel (dBm)         -24           : signal (dBm)         -41           Last message	Rx status Rx acq. status Rx freq. offset (Hz) Rx DEFR Edit mode TXI 13.579 048.0	On Acquisition -12 29 Coff F_LVL Okay Common 38 intf: status 38 intferface	Re-acquire Alarms ack. Start edit Cancel edit	Ebem 1 [Connect Ebem 1 Zeroize Reboot General ESEM 1	ted] Modem status free Reset free Carrier lock free Eth. bit sync. N Embed. ch. status Syn Control R Import free TA_AUPC Tests Alarms	Ready     Tx status       Itrai     Eb/No (dB)       Sync     Es/No (dB)       chroni     Rx level (d       mote     Rx signal (i       Export        Loop back	On         NRx status           IBm)         -19.00         NRx act, status           1         12.33         Rx freq. of the status           0         16.52         Rx buffer f           1Bm)         -33         Rx BER           (dBm)         -49         Edit mode           Last message	On Acquisition fset (Hz) 897 III(%) 43 Off BBO_CFG Okay	Re-acquire Alarms ack. Start edit Apply edit Cancel edit
Symbol rate (kbps)     80       Mode     EE       Sub mode     Tu       Modulation     PP       Predistortion     CC       Coding     7/8TURI       Interleaving     Nx       Diff encoding     Diss       Scrambler     Sy       Overhead mode     Nx       Overhead rate (kbps)     Clock       Clock     Intr       Data loss option     Maintz	04.5     Plann       BEM     Symb       urbo     Mode       SK8     Sub r       Off     Demo       B0_4096     Equal       None     Codir       soled     Inter       Sync     Diffe       None     Scrar       0     Over       tainSync     Embe       20     09:28:22	ned DR (kbps) 21 bol rate (kbps) 2 e E E mode T odulation 1 flazer Di alizer Di relaving 7/8TU relaving Di mbler 2 rencoding Di mbler 2 rhead mode 1 frhead rate (kbps) edded channel Er er size (bytes) 1 er re-center C k In	11.812     1       304.5     X       BBEM     X       BBEM     X       Turbo     X       PSK8     X       BBC     X       RBO_4096     X       Sabled     X       Sabled     X       None     X       None     X       abled     X       0     X       abled     X       0     X       abled     X       D Sec     X       tternal     X	Modem clock ref Ext. clock (MHz) Modem delay (ms) Doppler Doppler shift (Hz) Doppler shift (Hz) Doppler acc. (Hz/s Encryption status Encryption sync Encryption login Embed. ch. status Temperature (C)	AutoSense 10 38.1 0 8.2 0 0 0 0 0 0 0 0 0 0 0 0 0	Eb/Ne	n tests	ass	BERT Rese BERT Tx er BERT Tx pr BERT Rx er BERT Sync. BERT Sync. BERT Sync. BERT Sync. BERT Sync. BERT Sync. BERT Sync. BERT Sync. BERT Sync.	BERT stat. Inject bit f able On ttern ZT023 able On ttern ZT023 loss (s) 10 loss (s) 10 lo	irror
Configure 4. I.A.W the Verify the	re the EBEM2 e SAA's. (SAT at TSGT, EBE	⁻ Loop) See Co EM2 is lock.	onfiguration b	oelow.							
5. Configure is free of	re BER TESTE f any errors. In	ER in the MOD nject 1 Error an	EM, start the d see it.	BER tes	and verify test						

PROCEDURE / REPORT OF TEST № 1.8.1							
TEST NAME: BER stability Test	ELEMENT UNDER TEST: Satellite	e System	PROJECT: TSGT-DSO				
Ebem 2 [Connected]  Ebem 2 Modem status Recet	eady Tx status On ARx status On ARx status Con Arguinting Arguinting	Ebern 2 [Connected]	tatus On Rx status On Re-acquire				
Zeroize     Carrier lock     N       Eth. bit sync.     Nk       Reboot     Embed. ch. status     Nk       Control     Rk       Import     Import	Price         Revel         Complex         Revel         <	Zeroize         Carrier lock         Normal         Eh           Eth. bit sync.         No Sync         Es/N           Reboot         Embed. ch. status         Syndrroni         Rx la           Control         Remote         Rx si         Import         Export	Ver (ubit)         -19:00         pr(K adu; status         Padulstott         Alarms ack.           lo (dB)         11.21         Rx freq. offset (Hz)         -11         Start edit           o (dB)         15.41         Rx buffer fill(%)         44         Apply edit           evel (dBm)         -31         Rx BER          Cancel edit           ignal (dBm)         -48         Edit mode         Off				
General     ESEM     ITA_AUPC     Tests     Alarms       Tx     Freq. (MHz)     1212.569       Serial DR (kbps)     2048.0       Symbol rate (kbps)     804.5       Mode     EBEM       Sub mode     Turbo       Modulation     PSK8       Predistortion     Off       Coding     7/8TURB0_4096       Interleaving     None       Diff encoding     Disabled       Scrambler     Sync       Overhead rate (kbps)     0       Clock     Internal       Data loss option     MaintainSync       Time     03/11/2020 04:00:36	RX         Serial DR (kbps)       2048.0         Planned DR (kbps)       2011.012         Symbol rate (kbps)       2011.012         Sub mode       EBEM         Demodulation       PSK8         Demodulation       PSK8         Disabled       Doppler rate (Hz/s)         Diff encoding       Disabled         Diff encoding       Disabled         Overhead mode       None         Diff encoding       Disabled         Buffer ize (bytes)       0         Buffer ize (bytes)       15384         Buffer ize (bytes)       15384         Buffer ire-center       0 Sec         Clock       Internal	General ESEM ITA_AUPC Tests Alarms  Loop back Loopback test  POST Pass POST Pass Built-in test Built-in test Background BIT tests Pass Foreground BIT tests No Data FAT mode Disabled  Eb/No noise (dB) Off	BERT Reset BERT stat. Inject bit Error BERT Tx enable On BERT Tx pattern ERT Tx pattern DERT Rx pattern DERT Rx pattern DERT sync. loss (b) BERT sync. loss (b) BERT sync. loss (b) BERT bit error rate BERT sync. Synchronized BERT sync. BERT for count DERT Sync. Synchronized BERT sync. BERT out 1 BERT for count DERT sync. BERT sync. Synchronized BERT sync. BERT sync. BERT sync. BERT sync. Synchronized BERT sync. BERT s				
6. Configure the E I.A.W the SAA's Verify, that TSG	BEM3 . (SAT Loop) See Configuration below. T, EBEM3 is lock.						
7. Configure BER is free of any er	TESTER in the MODEM, start the BER test and verify test rors. Inject 1 Error and see it.						
## NATO UNCLASSIFIED



## NATO UNCLASSIFIED

	PROCEDURE / REPORT OF TEST № 1.8.1						
TEST NAME: BER : Test	stability	ELEMENT UNDER TEST: Satellite System			PROJECT: TSGT-DSO		
🗰 Ebem 4 [Connected	d]		8	🗱 Ebem 4 [Connected]			
C Ebem 4 Zeroize Reboot General ESEM ITA TX Freq. (Mriz) Serial DR (dops) Symbol rate (kbps) Mode Sub mode Modulation Predistorition Coding Interleaving Diff encoding Scrambler Overhead rate (kbp Clock Data loss option Time	Modem status Reset Carrier lock Eth. bit sync. Embed. ch. status Sync AUPC Tests Alarms 1212.569 2048.0 804.5 EBEM Turbo PSK8 Off 7/8TURB0_4096 None Disabled Sync None s) 0 03/11/2020 09:14:2	Ready Tx status On ARX   INTx level (dBm) -18.00 ARX   No Sync Es/No (dB) 10.61 Rx   No Sync Es/No (dB) 14.80 Rx   Indroni Rx level (dBm) -23 Rx   Renote Rx signal (dBm) -41 Ed   INS Sync Freq. (MHz) 1213.5   Freq. (MHz) 1213.5   Symbol rate (dbps) 2048.   Panned DR (ldps) 2048.   Panned DR (ldps) 2048.   Panned DR (ldps) 2111.8   Symbol rate (dbps) 2048.   Panned DR (ldps) 2111.8   Symbol rate (dbps) 004.9   Equalizer Disable   Coding 7/8TURBO   Interleaving None   Differ encoding Disable   Overhead mode None   Differ recenter 0 Ser   Buffer Enable   Buffer recenter 0 Set   Clock Intern	Xx status On Re-acquire   Xx scq. status Aquisition Alarms ack.   Xx freq. offset (Hz) -12 Start edit   Xx buffer fill(%) 38 Apply edit   Cancel edit Cancel edit   idit mode Off   S29 Bit inff: status Bdp edit   S30 RX_OP Olay   S29 Bit inff: status Bdp edit   Bit inff: status Bdp edit Dapler   Bit inff: status Dapler   S30 Nodem delay (ms) 38.1   Doppler Doppler acc. (Hz/s) 0   Doppler acc. (Hz/s) 0   Nedem delay (ms) Sister   Bit fifterace Baster   Bit fifterace Bd edit   Doppler acc. (Hz/s) 0   Doppler acc. (Hz/s) 0   Doppler acc. (Hz/s) 0   Bit fifterace Baster   Bit fifterace Baster   Bit fifterace Bd edit   Bit fifterace <th>O Ebern 4   Modem status   Ready   Tx statu.     Reset   Tx level     Zeroize   Eth. bit sync.   No Sync.   Es/No (i     Eth. bit sync.   No Sync.   Es/No (i   Rx signal     Control   Remote   Rx signal     Control   Remote   Rx signal     General   ESEM   ITA_AUPC   Tests     POST   Pass   POST tests   Background BIT tests     Background BIT tests   No Data   FAT mode   Disabled     Eb/No noise (dB)   Off   X</th> <th>US ON PRX status ON Re-acquire (dBm) -18.00 PRX acq, status Acquisition Alarms ack. (db) 13.14 RX freq, offset (Hz) 896 31.17.33 RX buffer fill(%) 49 Apply edit (dBm) -31 RX BER &lt; al (dBm) -47 Edit mode Off Last message TX_OP Okay BERT Reset BERT stat. Inject bit Error BERT TX enable On BERT TX enable On BERT RX pattern ZTo23rd BERT Rync. loss (h) 1 BERT sync. loss (h) 1 BERT for crort O BERT reor count O BERT reor count O BERT reor count 1 BERT loss count 1 BERT his cerror O BERT reor count 1 BERT his count 1 BERT his cerror O BERT reor count 1 BERT his cerror O BERT reor count 1 BERT his c</th> <th></th>	O Ebern 4   Modem status   Ready   Tx statu.     Reset   Tx level     Zeroize   Eth. bit sync.   No Sync.   Es/No (i     Eth. bit sync.   No Sync.   Es/No (i   Rx signal     Control   Remote   Rx signal     Control   Remote   Rx signal     General   ESEM   ITA_AUPC   Tests     POST   Pass   POST tests   Background BIT tests     Background BIT tests   No Data   FAT mode   Disabled     Eb/No noise (dB)   Off   X	US ON PRX status ON Re-acquire (dBm) -18.00 PRX acq, status Acquisition Alarms ack. (db) 13.14 RX freq, offset (Hz) 896 31.17.33 RX buffer fill(%) 49 Apply edit (dBm) -31 RX BER < al (dBm) -47 Edit mode Off Last message TX_OP Okay BERT Reset BERT stat. Inject bit Error BERT TX enable On BERT TX enable On BERT RX pattern ZTo23rd BERT Rync. loss (h) 1 BERT sync. loss (h) 1 BERT for crort O BERT reor count O BERT reor count O BERT reor count 1 BERT loss count 1 BERT his cerror O BERT reor count 1 BERT his count 1 BERT his cerror O BERT reor count 1 BERT his cerror O BERT reor count 1 BERT his c		
In the set of the term   Configure the EBEM5     In the set of the se							
11. Configuration is free	11.   Configure BER TESTER in the MODEM, start the BER test and verify test is free of any errors. Inject 1 Error and see it.						

## NATO UNCLASSIFIED



## Appendix F Key Personnel Requirements

 Table below lists the key personnel and required certification experience to be met. In exceptional circumstances, extensive relevance experience may be considered in lue of official certificates

No	Key Personnel	Requirements
1	Project Manager	Responsible for project management, performance and completion of tasks and delivery orders. Establishes and monitors plans and schedules and has full authority to allocate resources to insure that the established and agreed upon plans and schedules are met. Manages costs, technical work, project risks, quality, and corporate performance. Manages the development of designs and implementation plans. Establishes and maintains contact with Purchaser, Subcontractors, and project team members. Provides administrative oversight, handles contractual matters and serves as a liaison between the Purchaser and corporate management. Ensures that all activities conform to the terms and conditions of the Contract and Work Package procedures.
1.1	Certification	Degree in management, engineering, or business administration. Formal certification through Project Management Institute or equivalent source.
1.2	Experience	At least seven years in project management. At least two years as the project manager for an effort of similar scope, preferably including the application of a formal project management methodology such as PRINCE2.
2	ISS Manager	ISS Manager will conduct the ISS Program and act as the interface with the Purchaser on all ISS matters. They will provide and implement the ISS Plan and manage all processes pertaining to its delivery. Supervises the efforts of other service personnel in the execution of assigned tasks.
2.1	Certification	Degree.
2.2	Experience	At least seven years in ISS Management. At least two years as the ISS manager for an effort of similar scope, preferably including the application of a formal service management methodology.
3	Technician	Technicians will assist in planning, synchronizing, scheduling, and tracking of TSGT assets for preventative maintenance on all NATO CIS equipment based on the Central, Operational, and Deployable Service Level Agreements; Assist in scheduling and tracking capability of activities in support of operations, exercises, projects static Communications Information Systems (CIS) and Deployable CIS (DCIS); Assists in directing, supervising, planning, coordinating, monitoring and reporting upon all technical work carried out on PMI activities & ensure that all technical work is performed in line with Agency's, industrial and/or military standards;

No	Key Personnel	Requirements
		Develop detailed analysis of system deficiencies and provides advice on technical solutions in line with existing standards to ensure operational readiness for all customers and deployable Operational Systems Owners; Assist and monitor assigned technical tasks efficiently to ensure that they can be executed in line with set target dates. Explain and provides system technical & logistical advice to senior management & initiate necessary action to ensure that set maintenance and project targets are met; Assist with design and configuration documentation on TSGT & UTSGT assigned projects and systems, including required operating procedures and processes. Assist ISS Manager with the Implementation of procedures, tools and techniques for monitoring and managing performance of systems under maintenance and provides official reports; Assist and monitor all CIS equipment discrepancies are fully identified, investigated, documented, reported and implements corrective actions in accordance with NCI Agency directives; Assist with Key Performance Indicator (KPI) targets, and monitors progress against agreed quality and performance criteria. Provides effective feedback, throughout the performance management cycle, to ensure optimum performance
3.1	Certification	Higher vocational training in a relevant discipline, (such as, Telecommunications, Electronics, Electrical, or Computer Engineering) with 2 years of post-related experience; Or a secondary educational qualification with 4 years post-related experience;
3.2	Experience	Basic knowledge of the following transmission related topics: Knowledge of Transportable Satellite Communications equipment and be able to carry out in field/workshop repairs. Process a high level of understanding with respect to; Energy per bit to noise power spectral density ratio versus Bit Error Rate; Effective Isotropic Radiated Power calculations; Fourier analysis; Phase, Vector and Spectrum analysis; Various modulation techniques; Error coding theory; Fresnel zones. Basic mechanical and electrical engineering skills for deployable terminals; Elevation and Azimuth motor drives, servo drives, mechanical and electrical sensors and transducers; Basic knowledge of Fibre Optic measurements techniques, Single Mode and Multi-mode, on industrial and/or military tactical cabled networks; Understanding IP basics of Local and Wide Area Networking; Experience reading complex system diagrams (electrical and mechanical) and fault finding techniques in Super High frequency (SHF) band based deployable transmission systems;

No	Key Personnel	Requirements
		Fault finding experience in complex SHF based transmission system including systems with various antenna configurations; Recognizing digital Modulation Techniques: Phase, Frequency and Amplitude Shift Keying and various Analogue and Angle Modulation Techniques; Knowledge on performing measurements on antenna and sub-units: Low Noise Amplifier, Low Noise Block down converter, orthomode transducer Radio Frequency, microwave & electronic components; Configuring data test equipment to test radio based transmission systems in line with IP protocols (RFC 2544) and Data communication protocols; Knowledge of reconfiguring satellite systems in line with provided parameters, Timing, Error coding, modulation, Data rate, Bandwidth, Frequency Offsets; Knowledge of applying Non Ionizing Radiation safety measurements in line with ICNIRP (International Commission on Non-Ionizing Radiation Protection) and NATO standard agreement (STANAG) 2345ed3; Advanced understanding of power cabling and associated sub- systems, grounding and bonding, copper based structured cabling, an advanced understanding of fibre based structured cabling, working understanding of fibre optic modems, line drivers, media convertors; Good working knowledge of system network troubleshooting techniques utilising complex and diverse test equipment and software tools.